

CONSTRUCTION OF

PROJECT NAME

PROJECT NO. ##-####

SPECIAL PROVISIONS

SECTION W – WATER

The following Special Provisions supplement and amend the Standard Specifications for Public Works Construction 2015 Edition (Greenbook). These Special Provisions have been arranged into a format that parallels the Greenbook.

Bidders with pre-bid inquiries regarding the Work covered in this Section should be directed to Purchasing at (951) ###-####.

Prepared By:

Date

Reviewed:

Date

SECTION W – WATER

Table of Contents

| | |
|------------------------------------------------------------------------------------------------------------------|------------|
| SECTION 2 - SCOPE AND CONTROL OF WORK | W-1 |
| 2-5 PLANS AND SPECIFICATIONS..... | W-1 |
| SECTION 4 - SCOPE AND CONTROL OF WORK | W-1 |
| 4-1.1.1 Buy-American Clause..... | W-1 |
| SECTION - 10 AGENCY STANDARD DRAWINGS | W-1 |
| 10-1. STANDARD WATER AND WASTEWATER CONSTRUCTION DRAWINGS..... | W-1 |
| SECTION 209 – PRESSURE PIPE | W-2 |
| 209-1.1.1 General..... | W-2 |
| 209-1.1.1 General..... | W-2 |
| 209-1.1.2 Materials..... | W-4 |
| 209-1.1.2 Materials..... | W-4 |
| SECTION 212 – WATER AND SEWER SYSTEM VALVES AND APPURTENANCES | W-4 |
| 212-2 FLANGED AND THREADED CONNECTIONS..... | W-4 |
| 212-2.5 Flange, Coupling, and Harness Bolts, Nuts, and Washers..... | W-5 |
| 212-2.5.2 Flange, Coupling, and Harness Bolts, Nuts, and Washers for Above-Ground Ferrous or Plastic Piping..... | W-5 |
| 212-2.5.3 Applications in Corrosive, High-Chloride, or Saltwater Environments..... | W-6 |
| 212-2.7 Flange Gaskets..... | W-6 |
| 212-2.8.3 Flange Insulating Kits..... | W-6 |
| 212-2.9 Mastic and Tape-Wrap Systems..... | W-7 |
| 212-3 PIPE HANGERS AND SUPPORTS, CASING SPACERS, AND WALL PENETRATIONS..... | W-7 |
| 212-3.1.1 General..... | W-7 |
| 212-3.1.1 Materials..... | W-7 |
| 212-3.2 Casing Spacers..... | W-8 |
| 212-3.3 Wall Pipes, Seep Rings, and Penetrations..... | W-8 |
| 212-3.3.1. General..... | W-8 |
| 212-3.4 Rubber Annular Hydrostatic Sealing Devices..... | W-9 |
| 212-3.4.1 General..... | W-9 |
| 212-4 VALVE ACTUATORS, EXTENSIONS, AND VALVE BOXES..... | W-9 |
| 212-4.2.2 Valve Extension Stems..... | W-9 |
| 212-4.2.3 Valve Can and Cover for Buried Valves..... | W-9 |
| 212-4.2.3.1. General..... | W-9 |
| 212-4.3 Valve Operators for Above-Ground Valves..... | W-10 |
| 212-4.3.1 General..... | W-10 |
| 212-5 VALVES..... | W-10 |
| 212-5.1.1 General..... | W-10 |
| 212-5.1.3 Design Options..... | W-10 |
| 212-5.1.4 Tapping Valves..... | W-11 |
| 212-5.1.5 Tapping Sleeves..... | W-11 |

| | |
|------------------------------------------------------------------------------------------------------|------|
| 212-5.1.5 Tapping Sleeves. | W-11 |
| 212-5.2 Butterfly Valves. | W-11 |
| 212-5.2.1 General. | W-12 |
| 212-5.3 Plug Valves. | W-12 |
| 212-5.3.1 General. | W-12 |
| 212-5.4 Ball Valves. | W-12 |
| 212-5.4.1 General. | W-12 |
| 212-5.5 Check Valves. | W-13 |
| 212-5.5.1 Swing-Check Valves. | W-13 |
| 212-5.5.1.1 General. | W-13 |
| 212-5.5.1.3 Design Options. | W-13 |
| 212-5.5.4 Slanting-Disc Check Valves. | W-13 |
| 212-5.6 Air Release, Air/Vacuum, and Combination Air Valves. | W-13 |
| 212-5.6.1 General. | W-14 |
| 212-5.7 Diaphragm-Actuated Pilot-Control Valves. | W-14 |
| 212-5.7.1 General. | W-14 |
| 212-5.7.2 Materials. | W-15 |
| 212-6 HYDRANTS. | W-15 |
| 212-6.1 Fire Hydrants. | W-15 |
| 212-6.1.1 General. | W-15 |
| 212-6.1.1 General. | W-16 |
| 212-7 BACKFLOW PREVENTION DEVICES. | W-16 |
| 212-7.2 Double Check (DC) Valve Backflow Prevention Assemblies. | W-16 |
| 212-7.3 Reduced-Pressure (RP) Backflow Prevention Assemblies. | W-16 |
| 212-8 COUPLINGS. | W-16 |
| 212-8.1 Bolted Sleeve Type Couplings. | W-16 |
| 212-8.1.1 General. | W-17 |
| 212-8.2 Flanged Coupling Adaptors. | W-17 |
| 212-8.2.1. General. | W-17 |
| 212-8.3 Coupling Restraint Systems. | W-18 |
| 212-8.4 Grooved and Shouldered Couplings and Joints. | W-18 |
| 212-8.4.1 General. | W-18 |
| 212-9 EXPANSION JOINTS. | W-18 |
| 212-9.1 Double-Ball Expansion Joints. | W-18 |
| 212-9.1.1 General. | W-18 |
| 212-10 SERVICE LATERALS, METERS, AND METER BOXES. | W-19 |
| 212-10.3 Corporation Stops, Angle Meter Valves, Service Saddles and Other Service Materials. | W-19 |
| 212-10.4 Meters. | W-20 |
| 212-10.6 Meter Boxes. | W-20 |
| 212-10.6.1 General. | W-21 |
| 212-10.6.2 Dimensions. | W-21 |
| 212-11 PRESSURE GAUGES. | W-21 |
| 212-11.1 Stem-Mounted Pressure Gauges. | W-21 |
| 212-11.1.1 General. | W-21 |
| 212-11.1.2 Materials. | W-22 |
| 212-11.1.3 Design Options. | W-22 |
| 212-11.2 Flanged In-Line Sensor Sleeve Style Pressure Gauges. | W-22 |
| 212-11.2.1 General. | W-22 |
| 212-12 PAINTING, INTERIOR LINING, AND EXTERIOR COATING. | W-23 |
| 212-12.1 Lining and Coating of Ferrous Valve, Hydrant, Valve Operator, Meter, | |

| | |
|---------------------------------------------------------------------------------------------------------------------|-------------|
| Coupling, Expansion Joint, Spool, Fitting, and Backflow Preventer Surfaces..... | W-23 |
| 212-12.1.1 General..... | W-23 |
| SECTION 306 – OPEN TRENCH CONDUIT CONSTRUCTION | W-24 |
| SECTION 306-1.5.2 Permanent Resurfacing..... | W-24 |
| 306-2 DELIVERY, STORAGE, HANDLING AND PROTECTION OF PIPELINE MATERIALS, FITTINGS, VALVES, AND APPURTENANCES..... | W-24 |
| 306-2.2 Shipment and Delivery..... | W-24 |
| 306-2.2.1 General..... | W-24 |
| 306-2.3 Storage..... | W-24 |
| 306-2.5 Protection of Pipe Interiors..... | W-24 |
| 306-2.7 Shutdowns of Existing Pipelines..... | W-25 |
| 306-2.7.1 General..... | W-25 |
| 306-2.7.3 Temporary Bypass..... | W-25 |
| 306-8 PREFABRICATED PRESSURE PIPE..... | W-25 |
| 306-8.1 General..... | W-25 |
| 306-8.2 Ductile Iron Pipe..... | W-26 |
| 306-8.2.2.1 Push-on Joints..... | W-26 |
| 306-8.2.2.3 Installation of Polyethylene (PE) Film Wrap on Iron Fittings..... | W-26 |
| 306-8.8.2.1 General..... | W-26 |
| 306-8.8.4 Service Connections..... | W-26 |
| 306-8.8.6 Fire Hydrant Installation..... | W-26 |
| 306-8.9 Hydrostatic Pressure Test..... | W-26 |
| 306-8.9 Hydrostatic Pressure Test and Flushing..... | W-27 |
| 306-8.9.2.2 Preparation..... | W-27 |
| 306-8.9.2.2.1 Initial Flushing..... | W-27 |
| 306-8.9.2.4 Test Procedure..... | W-28 |
| 306-8.9.4 Disinfection..... | W-29 |
| 306-8.9.4.1 General..... | W-29 |
| 306-8.9.4.2 Submittals..... | W-29 |
| 306-8.9.4.3 Potable Water System Disinfection Procedures..... | W-29 |
| 306-8.9.4.5 Dechlorination and Flushing..... | W-30 |
| 306-8.9.4.6 Bacteriological Sampling and Testing..... | W-31 |
| 306-12 BACKFILL..... | W-33 |
| 306-12.4 Jetted Trench Backfill..... | W-33 |
| 306-12.4.1 General..... | W-33 |

SECTION 2 - SCOPE AND CONTROL OF WORK

2-5 PLANS AND SPECIFICATIONS.

2-5.3.3 Shop Drawings.

Add the following to Table 2-5.3.3:

TABLE 2-5.3.3

| Item | Subsection No. | Title | Subject |
|------|----------------|-------------------|------------------------------------------------------------------------------------------------------------|
| 7 | 212-1.1 | Submittal Package | Water and Sewer System Valves and Appurtenances |
| 8 | 306-8.9.4 | Disinfection | Disinfection, Testing, Flushing, and Dechlorinating, Discharge to Sewer or Storm Drain, Laboratory Testing |

SECTION 4 - SCOPE AND CONTROL OF WORK

Add the following subsection:

4-1.1.1 Buy-American Clause.

Unless otherwise shown, all materials used for water system construction shall be made in the United States of America.

Add the following section:

SECTION - 10 AGENCY STANDARD DRAWINGS

10-1. STANDARD WATER AND WASTEWATER CONSTRUCTION DRAWINGS.

Agency standard drawings governing construction in the City of Corona include the following:

| | |
|--------------|--------------------------------------------|
| Standard 301 | Sewer Lateral on New Sewer |
| Standard 302 | Standard Manhole |
| Standard 303 | Drop Manhole |
| Standard 304 | Sewer Lateral Connection on Existing Sewer |
| Standard 305 | Not Used |
| Standard 306 | Not Used |
| Standard 307 | Sewer Lateral Terminal Cleanout |
| Standard 308 | Sewer Pipe Bedding and Trench Details |
| Standard 309 | Steel Casing for Gravity Flow Pipe |
| Standard 310 | Concrete Slope Anchors |
| Standard 401 | Concrete Thrust Blocks Details |
| Standard 402 | Steel Casing for Pressure Pipe |
| Standard 403 | Not Used |
| Standard 404 | Potable Water Sample Station |

(UPDATED: 07-21)

| | |
|---------------|-----------------------------------------------------------------------------------|
| Standard 405 | Guard Post Details |
| Standard 406 | Potable and Reclaimed Water Pipe Bedding and Trench Details |
| Standard 407 | Potable Water Line Crossing Under Existing Utility |
| Standard 407R | Reclaimed Water Line Crossing Under Existing Utility |
| Standard 408 | 1" Potable Water Service Connection Detail with Fire Sprinkler Service |
| Standard 409 | 1½" and 2" Potable Water Service Connection Detail with Fire Sprinkler Service |
| Standard 410 | Pressure Regulating Station |
| Standard 411R | Reclaimed Water Irrigation Sign |
| Standard 412 | 6" Potable Water Fire Hydrant Installation |
| Standard 412R | 6" Reclaimed Water Fire Hydrant Installation |
| Standard 413 | 1" or 2" Potable Water Combination Air and Vacuum Release |
| Standard 413R | 1" or 2" Reclaimed Water Combination Air and Vacuum Release |
| Standard 414 | 1" Potable Water Service Connection Detail without Fire Sprinkler Service |
| Standard 414R | 1" Reclaimed Water Service Connection Detail |
| Standard 415 | 1½" and 2" Potable Water Service Connection Detail without Fire Sprinkler Service |
| Standard 415R | 1½" and 2" Reclaimed Water Service Connection Detail |
| Standard 416 | 6" Potable Water Fire Hydrant Blow-Off Assembly |
| Standard 416R | 6" Reclaimed Water Fire Hydrant Blow-Off Assembly |
| Standard 417 | Double Check Detector Assembly |
| Standard 418 | Adjustable Pipe Support |
| Standard 419 | Pipeline Separation Requirements |
| Standard 420 | Resilient Wedge Gate Valve Installation |
| Standard 421 | Cut-in Tee |
| Standard 422 | Valve Box and Valve Stem Extension |
| Standard 423 | Not Used |
| Standard 424 | Meter Room Potable Water Service Connection Detail |
| Standard 425 | Courtyard Potable Water Service Connection Detail |
| Standard 426 | Potable Water Compound Flow Meter |
| Standard 426R | Reclaimed Water Compound Flow Meter |
| Standard 427 | Not Used |
| Standard 428 | Reduced Pressure Principle Backflow Assembly |
| Standard 450 | Two Wire Test Station |
| Standard 451 | Not Used |
| Standard 452 | Casing Test Station |
| Standard 453 | Insulator Test Station |
| Standard 454 | Test Station Box and Wiring |
| Standard 455 | Test Station Locations in Street Right-of-Way |
| Standard 456 | Alumino-Thermic (CAD) Welding and Pin Brazing |
| Standard 457 | Bonding for Pipe Joints and Fittings |
| Standard 458 | Insulating Joint |

SECTION 209 – PRESSURE PIPE

209-1.1.1 General

Delete entire subsection and substitute with the following:

209-1.1.1 General

(UPDATED: 07-21)

This subsection specifies ductile iron pipe used for pressure piping applications for water and reclaimed water pressure pipes, sewage force mains, and other liquids. Pipe shall be fully self-restrained without the use of thrust blocks, notwithstanding the requirement for supplemental thrust blocks in City of Corona Standard Drawing 401.

PVC, HDPE, CML&C steel, asbestos cement, or concrete cylinder pipe (CCP) pressure pipe shall not be used in the City of Corona without written approval from the Engineer. Acceptable manufacturers are listed in Table 209-1.1.1:

TABLE 209-1.1.1

| Item | Manufacturer |
|-------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------|
| Ductile-Iron Pipe | American Cast Iron Pipe Company (ACIPCO) |
| | Pacific States Cast Iron Pipe Co Div. McWane, Inc. |
| | U.S. Pipe and Foundry |
| Ductile-Iron Pipe Fittings | American Cast Iron Pipe |
| | Tyler Union Div. McWane, Inc. |
| | U.S. Pipe and Foundry |
| Push-on Joints | American Cast Iron Pipe "Fastite" |
| | Pacific States Cast Iron Pipe Co Div. McWane, Inc. |
| | U.S. Pipe and Foundry "Tyton" |
| Restrained Joints – Locking Gasket Type | American Cast Iron Pipe "Fast-Grip" |
| | Pacific States Cast Iron Pipe Co Div. McWane, Inc. "Sure-Stop" |
| | U.S. Pipe and Foundry "Field-Lok" |
| Tee-Head Bolts and Hex Nuts on Mechanical Joints | NSS Industries Corten Tripac |
| Restrained Joints - Third-Party Follower-Gland-Type Mechanical Joint Restraints for Ductile Iron Pipe | EBAA Iron Megalug Series 1100 #1100 for new MJ fittings 3"-48" #1100SD restraint for existing MJ fittings 3"-48" |
| | Ford Uni-Flange Series 1300 Restrained End Cap for MJ fittings 4"-16" |
| | Ford Uni-Flange Series 1400 for MJ fittings 4"-36" |
| | |
| Third-Party Follower-Gland-Type Mechanical Joint Restraints for Joining to Existing PVC Pipe | EBAA Iron Megalug Series 2000 #2000PV for new MJ fittings 4"-24" #2000SV for existing MJ fittings 4"-24" |
| | Ford Uni-Flange Series 1500 Circle Lock for MJ fittings 4"-24" |
| | |
| Third-Party Transition Coupling for Joining DI Pipe to AC Pipe | Romac 501-13.55 x 14 (L) or 501-13.55 x 14.44 x 14 (L) if required. Transition Coupling |
| | Accepted Equals |
| Third-Party Ductile Iron Pipe Restraint Harness for Push-on Bells (For DIP only. Do not use on PVC) | EBAA Iron Megalug Series 1700 Restraint Harness 3"-36" |
| | Ford Uni-Flange Series 1450 |
| Flanged Coupling Adaptor Restraints | EBAA Iron Megaflange Series 2100 3"-48" |
| | Ford Meter Box Company, Uniflange w/ UFR 1400 3"-24" |
| | JCM Industries, Inc. Style 301 |
| | Romac Industries RFCA |
| | Smith Blair, Inc Style 912, "Flange Lock" DIP 3"-12" |
| Shop Coat on Buried Pipe | Koppers 11-S Primer |
| Polyethylene Encasement | Christy's "AWWA Polywrap" |

(UPDATED: 07-21)

| | |
|-------------------------------|--------------------------------------------------------------------------------------------------------------------------------------|
| | Dupont Alathon Northtown Company Trumbull Industries, Inc. V-Bio (Ductile Iron Pipe Research Association) Accepted Equal |
| Ceramic Epoxy Lining | Induron Protecto 401 |
| Field Coatings on Buried Pipe | Koppers Bituplastic No 33 |

209-1.1.2 Materials.

Add the following to Table 209-1.1.2:

TABLE 209-1.1.2

| Item | Material | Specification | |
|--------------------------------------|----------------------------------------------------------------------------------------------|-----------------------------------------------|--------------------|
| Pipe | Minimum Wall Thickness | Pipe with Threaded Flanges | Thickness Class 53 |
| Interior Lining and Exterior Coating | Ceramic Epoxy Interior Lining, where shown on Plans – required for pipes transporting sewage | Minimum 20% by volume ceramic quartz pigment. | |
| Joints | Restrained Style (Required on all new pipe construction) | Locking gasket style | |
| Fittings | Style | Mechanical joint (with restraint) or flanged | |
| Ductile Iron Pipe Joint Restraints | Style | Locking gasket style | |

209-1.1.2 Materials.

Delete the following from Table 209-1.1.2:

TABLE 209-1.1.2

| Item | Material | Specification |
|--------------------------------------|------------------|--------------------------------------------------------|
| Fittings | Style | Push-on (standard) or restrained joint (as shown). |
| Alternate to Polyethylene Encasement | Pipe Finish Coat | 15 mils (375 µm) MDFT field-applied bitumastic coating |

SECTION 212 – WATER AND SEWER SYSTEM VALVES AND APPURTENANCES

212-2 FLANGED AND THREADED CONNECTIONS.

212-2.5 Flange, Coupling, and Harness Bolts, Nuts, and Washers.

Add the following:

Acceptable manufacturers are listed in Table 212-2.5.

TABLE 212-2.5

| Item | Manufacturer |
|--------------------------------------------------------|-------------------------------------------------|
| Anti-Seize Compound for Stainless Steel Bolts and Nuts | Bostik Never Seez |
| | Christy's Antiseize |
| | Husk-It Husky Lube O-Seal |
| | Loctite |
| | Permatex |
| | Ramco Antiseize |
| | Ramco TRX-Synlube |
| Bolts and Nuts | A&G Engineering Company |
| | Industrial Threaded Products, Inc. (wholesaler) |
| | Le Jeune Bolt Co. (L) |
| | Nucor Fasteners (n) |
| | Pacific Coast Bolt (wholesaler) |
| | Texas Bolt Company (TB) |
| | Tripac Fasteners (wholesaler) |
| | Unytite, Inc. (UNY) |
| | Western Pacific Products (wholesaler) |
| Buried Bolt Coatings | 3M Company (EC 244) |
| | Carboline Bitumastic No 50 |
| | Engard Coatings 858 |
| | Protecto-Wrap Company |
| | Carboline Bitumastic No. 50 |
| | Engard Coatings 858 |
| | Tnemec Co. (46-465 H.B. Tnemecol) |

212-2.5.2 Flange, Coupling, and Harness Bolts, Nuts, and Washers for Above-Ground Ferrous or Plastic Piping.

Delete the following from Table 212-2.5.2:

TABLE 212-2.5.2

| Item | Material | Specification |
|----------------------------------------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Bolts for Above-Ground Ferrous Installations | Zinc-Plated Carbon Steel | ASTM A307 Grade B. Heavy hexagon series ANSI B1.1 Class 2A fit Class 3A fit may be used for holes tapped for studs. 1/4" to 1/2" (6mm-12.5mm) shall project through tightened nut. Threads may be either cut or cold-formed. Threading per ANSI/ASME B18.2.1. |

(UPDATED: 07-21)

| | | |
|---------------------------------------------|--------------------------|---------------------------------------------------------------------------------------------------|
| | | Bolt-Head Identification Mark – “A307B” |
| Nuts for Above-Ground Ferrous Installations | Zinc-Plated Carbon Steel | ASTM A563. Heavy hexagon series ANSI B1.1 Class 2B fit. Threading per ANSI/ASME B18.2.2. |
| Coating for Existing Bolts and Nuts | Non-Oxide Grease | Use on zinc-plated carbon steel hardware |

212-2.5.3 Applications in Corrosive, High-Chloride, or Saltwater Environments.

Delete the following from Table 212-2.5.3:

TABLE 212-2.5.3

| Item | Material | Specification |
|-----------------------------------|----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|
| Coating for Buried Nuts and Bolts | AWWA C217 Petrolatum Wax and Wax-Tape System | Primer, wax, and 40-mil (1 mm) tape per AWWA C217. 1” (25 mm) minimum tape overlap with 1.5-mil (40 µm) clear metallocene resin tape outer wrap. |

212-2.7 Flange Gaskets.

Add the following:

Acceptable manufacturers are listed in Table 212-2.7:

TABLE 212-2.7

| Item | Manufacturer |
|---------------------------------|---------------------------------------------------------|
| NSF 61-Listed Flange Gaskets | Bluegard Div. Garlock, Inc. Style 98206 |
| | PSI (Pipeline Seal and Insulator, Inc.) “Linebacker 61” |
| | U.S. Pipe and Foundry “Flange-Tyte” |
| Flange Gaskets – Cloth-Inserted | Bluegard Div. Garlock, / Inc. Style 5000 |
| | John Crane (Cranite) |
| | Johns Manville 60 |
| | Tripac Style 5000 |
| Flange Gaskets – Neoprene | Bluegard Div. Garlock, Inc. Style 2000 |
| | John Crane (Cranite) |
| | Johns Manville 60 |
| | Tripac Style 2000 |

212-2.8.3 Flange Insulating Kits.

Add the following:

Acceptable manufacturers are listed in Table 212-2.8.3.2.

TABLE 212-2.8.3.2

(UPDATED: 07-21)

| Item | Manufacturer |
|--------------------------------|------------------------------------------------|
| Flange Insulation Kit Products | APS Advance Products & Systems, Inc |
| | Calpico, Inc. |
| | Central Plastics Company |
| | Corrpro Corrosion Div Control Products Company |
| | Farwest Corrosion Control |
| Insulating Reducing Bushings | PSI (Pipeline Seal and Insulator, Inc.) |
| | Christy's |
| Insulating Gaskets | Calpico, Inc. |
| | PSI Linebacker "Type E" |

212-2.9 Mastic and Tape-Wrap Systems.

Delete section in its entirety.

212-3 PIPE HANGERS AND SUPPORTS, CASING SPACERS, AND WALL PENETRATIONS

212-3.1.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-3.1.1.

TABLE 212-3.1.1

| Item | Manufacturer |
|--------------------------------------------------|---------------------------------------|
| Concrete Anchors – Epoxy Adhesive Anchor Systems | Hilti Corp. |
| | Simpson Strong Tie Co. "Epoxy-Tie" |
| | Reynolds |
| Pipe and Conduit Hangers | Grinnell Corporation "Anvil" |
| | Tripac Inc. |
| | Unistrut Corporation |
| Metal Bolted Framing Strut Systems | Tripac Inc. |
| | Unistrut Corporation |
| Fiberglass Channel Framing Systems | Champion Fiberglass "Champion Strut" |
| | Strut Tech Engineered Support Systems |
| | Unistrut Corporation |

212-3.1.1 Materials.

Delete the following from Table 212.3.1.2:

TABLE 212-3.1.2

| Item | Option | Specification |
|---------------------------------------------------|----------------|--------------------------------------------|
| Bolts (Connection Bolts and Anchor Bolts) – Steel | High Strength | ASTM A325 or ASTM A490. |
| | Carbon Steel - | With self-locking nuts or lock-washers and |
| | Galvanized | plain nuts |

(UPDATED: 07-21)

| | | |
|-------------------------------------------|---------------------------|--------------------------------------------------------------------|
| Concrete Anchors – Expansion Bolt Systems | Stainless Steel | SAE Type 316 |
| Powder Actuated Fastening Systems | Steel | AISI 1061. Hardness: 52-58 Rockwell C |
| | Galvanized Coating | ASTM B6333 – 2.1 mil (53µm) thickness – 1.30 oz./ft ² |
| Pipe and Conduit Hangers (Above Ground) | Galvanized Coating | ASTM A153 - 2.1 mil (53µm) thickness – 1.30 oz./ft ² |
| Washers | Carbon steel - Galvanized | Square or rectangular smooth beveled washers, tapered in thickness |
| | Galvanized Coating | ASTM A153 - 2.1 mil (53µm) thickness – 1.30 oz./ft ² |

212-3.2 Casing Spacers.

Add the following:

Acceptable manufacturers are listed in Table 212-3.2.

TABLE 212-3.2

| Item | Manufacturer |
|----------------------------------|--------------------------------------------------|
| Casing Insulators - Metallic | APS Advance Products & Systems, Inc./Model SSI |
| | Calpico/Model PX |
| | CCI Pipeline Systems |
| | Pipeline Seal and Insulator, Inc. (PSI) |
| | Smith Blair “800” Series |
| Casing Insulators – Non-Metallic | Pipeline Seal and Insulator, Inc. (PSI) “Ranger” |
| Casing End Seals Rubber | Advance Products & Systems, Inc./ Model AC |
| | Calpico/Model C |
| | Pipeline Seal and Insulator, Inc. (PSI) Model S |
| | Powerseal Pipeline Products Corp |
| Casing End Seals Heat Shrinkable | Caseal |
| | Raychem |

212-3.3 Wall Pipes, Seep Rings, and Penetrations.

212-3.3.1. General.

Add the following:

Acceptable manufacturers are listed in Table 212-3.3.1.

TABLE 212-3.3.1

(UPDATED: 07-21)

| Item | Manufacturer |
|------------------------------------------------|----------------------------------------------------------------------------------------|
| PVC Pipe Penetration Sleeve with Weep Ring | Calpico, Inc. |
| | Pipeline Seal and Insulator, Inc. (PSI) "Century Line" (Type S-316) |
| PVC Wall Sleeve with Weep Ring | Pipeline Seal and Insulator, Inc. (PSI) "WS" Steel Wall Sleeve |
| Polyethylene Foam Filler for Pipe Penetrations | Dow Chemical Company "Ethaform" |
| | Hercules Inc Plastic Products Group Industrial Systems Department (Minicel backer rod) |
| | Pipeline Seal and Insulator, Inc. (PSI) "Cell-Cast" |

212-3.4 Rubber Annular Hydrostatic Sealing Devices.

212-3.4.1 General.

Add the following:

Acceptable manufacturers include the following:

TABLE 251-3.4

| Item | Manufacturer |
|--------------------------------------------|------------------------------------------------------------------|
| Rubber Annular Hydrostatic Sealing Devices | Calpico, Inc. "Pipe Linx" |
| | CCI Pipeline Systems "Wrap-it Link" (Type WL-SS) |
| | Pipeline Seal and Insulator, Inc. (PSI) "Link Seal" (Type S-316) |

212-4 VALVE ACTUATORS, EXTENSIONS, AND VALVE BOXES.

212-4.2.2 Valve Extension Stems.

Delete the following:

Extension stems on valves shall be furnished and installed wherever the valve centerline is more than 4 feet (1.2 m) below the finish grade or water surface. The extension stem shall bring the nut to within 6 inches (150 m) below the finished grade or water surface. Stem extensions shall not be pinned to the valve operating nut.

Replace with the following:

Extension stems on valves shall be furnished and installed wherever the valve centerline is more than 5 feet below the finish grade or water surface. The extension stem shall bring the nut to 2 feet below the finished grade or water surface. Stem extensions shall not be pinned to the valve operating nut.

212-4.2.3 Valve Can and Cover for Buried Valves.

212-4.2.3.1. General.

Add the following:

Acceptable manufacturers are listed in Table 212-4.2.2.

TABLE 212-4.2.3.1

| Item | Manufacturer |
|------------------------|------------------------------------|
| Valve Boxes and Covers | Christy's G-5 |
| | Eisel Enterprises, Inc. |
| | Jensen Precast |
| | DFW Plastics Inc. |
| Valve Box Covers | Alhambra Foundry Company Ltd. |
| | Long Beach Iron Works, Inc. |
| | Neenah Foundry |
| | South Bay Foundry |
| | U S Foundry and Manufacturing Corp |
| | DFW Plastics Inc. |

212-4.3 Valve Operators for Above-Ground Valves

212-4.3.1 General.

Delete entire subsection and substitute with the following:

Above-ground valves shall have 2-inch operating nuts with position indicators and a locking cap over the operating nut.

212-5 VALVES.

212-5.1.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-5.1.1.

TABLE 212-5.1.1

| Item | Manufacturer |
|-------------------------------------------------------|---------------------------------------------|
| Resilient Wedge Gate Valves (Potable Water AWWA C515) | ACIPCO American Flow Control Series 2500 |
| | Clow Valve Series 2600 |
| | Kennedy Valve Div., McWane, Inc. Kenseal II |
| | M&H Valve Div. McWane Inc Style 7000 |
| | Mueller Co. Series 2360 |

212-5.1.3 Design Options.

Delete the Handwheel requirements in Table 212-5.1.3 and replace with the following.

TABLE 212-5.1.2

| Item | Option | Specification |
|-------------|---------------|----------------------|
|-------------|---------------|----------------------|

(UPDATED: 07-21)

| | | |
|-----------------------------|-----------|-------------------------------------------------------------------------------|
| Resilient Wedge Gate Valves | Handwheel | Required on above-ground valves or valves in vaults where shown on the Plans. |
|-----------------------------|-----------|-------------------------------------------------------------------------------|

212-5.1.4 Tapping Valves.

Add the following:

Acceptable manufacturers are listed in Table 212-5.1.4.

TABLE 212-5.1.4

| Item | Manufacturer |
|----------------|---------------------------------------------|
| Tapping Valves | ACIPCO American Flow Control Series 2500 |
| | Clow Valve Series F-6000 |
| | Kennedy Valve Div., McWane, Inc. Kenseal II |
| | M&H Valve Div. McWane Inc Style 3751 |
| | Mueller Co. Series H600 or H700 |

212-5.1.5 Tapping Sleeves.

Add the following:

Acceptable manufacturers are listed in Table 212-5.1.4.

TABLE 212-5.1.4

| Item | Manufacturer |
|--------------------------------------------------------------|-----------------------------------------|
| Stainless Steel Tapping Sleeves 12" and smaller | Dresser Piping Specialties (620 Series) |
| | Romac Industries (Style SSTIII) |
| | Smith Blair, Inc. (Model 663) |
| Stainless Steel Tapping Sleeves Greater than 12" in Diameter | Romac Industries (Style SSTIII) |
| | Smith Blair, Inc. (Model 663) |

212-5.1.5 Tapping Sleeves.

Delete entire subsection and substitute with the following:

Tapping sleeves shall be stainless steel. Gaskets shall provide a full circumferential seal on both sides of the tap capable of withstanding the specified test pressures or be a positive-seal-type gasket capable of withstanding specified test pressures. Flanges shall match adjacent valves. Size-on-size stainless-steel-type tapping sleeves will not be permitted. Outlet taps larger than 67 percent of tapped pipe size will not be permitted unless accepted in writing by the Engineer.

Tapping sleeves may be used for working pressures up to 150 psi. At higher pressures, tapping sleeves may only be used if express written approval is obtained from the DWP General Manager or designee.

212-5.2 Butterfly Valves.

(UPDATED: 07-21)

212-5.2.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-5.2.1.

TABLE 212-5.2.1

| Item | Manufacturer |
|--------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------|
| Butterfly Valves for Buried Service (Class 150B) | DeZurik "BAW" |
| | Henry Pratt Co. "Groundhog II" |
| Butterfly Valves for Use Above Ground with resilient seat on valve body (Class 150B) | DeZurik "BAW" with hand lever up to 4" with M series handwheel actuator 6" and larger |
| | Henry Pratt Co. Model 2FII with hand lever up to 4" with Pratt MDT operator 6" and larger |

212-5.3 Plug Valves.

212-5.3.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-5.3.1.

TABLE 212-5.3.1

| Item | Manufacturer |
|--------------------------------------------------------|---------------------------------------------------------|
| Eccentric Plug Valves and Actuators – Rectangular Port | DeZurik PEF |
| Eccentric Plug Valves and Actuators – Round Port | Henry Pratt Company "Ballcentric /Milliken Valve 3"-18" |

212-5.4 Ball Valves.

212-5.4.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-5.4.1.

TABLE 212-5.4.1

| Item | Manufacturer |
|-------------|---------------------|
|-------------|---------------------|

(UPDATED: 07-21)

| | |
|--------------------------------|------------------------------------------------------------------|
| Ball Valves – Metal Seated | APCO Willamette Valve and Primer Corporation List 26 Series 2600 |
| | Henry Pratt Company Bulletin BV-90 |
| Ball Valves – Resilient Seated | APCO Willamette Valve and Primer Corporation List 26 Series 2600 |
| | Henry Pratt Company Bulletin BV-90 |
| | Val-Matic Valve and Manufacturing Company “Ener-G” Series 4000 |

212-5.5 Check Valves.

212-5.5.1 Swing-Check Valves.

212-5.5.1.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-5.5.1.1.

TABLE 212-5.5.1.1

| Item | Manufacturer |
|--------------------|----------------------------------------------|
| Swing Check Valves | M&H Valve Div McWane Inc. Style 159 (4”-12”) |

212-5.5.1.3 Design Options.

Add the following to Table 212-5.5.1.3:

TABLE 212-5.5.1.3

| Item | Option | Specification |
|--------------------|--------------------|----------------------------------|
| Swing Check Valves | Position Indicator | Required on Valves 6” and Larger |

212-5.5.4 Slanting-Disc Check Valves.

Add the following:

Acceptable manufacturers are listed in Table 212-5.5.4.

TABLE 212-5.5.4

| Item | Manufacturer |
|---------------------------------------------------------------------------|--------------------------------------------------|
| Slanting Disc Check Valves with Controlled Opening and Closing – 14”- 60” | APCO Willamette Valve and Primer Corp Series 800 |

212-5.6 Air Release, Air/Vacuum, and Combination Air Valves.

(UPDATED: 07-21)

212-5.6.1 General.

Delete entire subsection and substitute with the following:

Air release, air/vacuum and combination air valves shall comply with AWWA C512, except where listed acceptable manufacturers include patented air release, air vacuum and combination air valves similar in function, but not design to AWWA C512. Said products shall be capable of passing all tests described in AWWA C512 Section 5.

Acceptable manufacturers are listed in Table 212-5.6.1.

TABLE 212-5.6.1

| Item | Manufacturer |
|------------------------------------------------------------------------|------------------------------------------------------------------------------|
| Air Release Valves (for working pressures to 175 psi) | ARI Flow Control Accessories D-040-C Series 1"- 2" D-015 Series 3"- 8" |
| Air Release Valves (for working pressures over 175 psi) | ARI Flow Control Accessories D-065 HF Series |
| Well Service Air Valves 3-inch and smaller | ARI Flow Control Accessories D-070 Series |
| Air and Vacuum Valves | ARI Flow Control Accessories D-040-C Series 1"- 2" S-015 Series 3"- 8" |
| Combination Air and Vacuum Valves | ARI Flow Control Accessories D-040-C Series 1"- 2" S-015 Series 3"- 8" |
| Vacuum Breaker Valve with Controlled Air Release | ARI Flow Control Accessories D-040-C Series |
| Air Release Valves for Wastewater | ARI Flow Control Accessories S-020 |
| Air and Vacuum Valves for Wastewater | ARI Flow Control Accessories D-020 or D-025 |
| Combination Air and Vacuum Valves for Wastewater | ARI Flow Control Accessories D-020 or D-025 |
| Combination Air and Vacuum Valves for Wastewater (All Stainless Steel) | ARI Flow Control Accessories |

Note: ARI Flow Control Accessories products are manufactured in Israel.

212-5.7 Diaphragm-Actuated Pilot-Control Valves.

212-5.7.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-5.7.1.

TABLE 212-5.7.1

| Item | Manufacturer |
|------------------|---------------------------------|
| Diaphragm Valves | Cla-Val Company (no exceptions) |

(UPDATED: 07-21)

212-5.7.2 Materials.

Delete entire subsection and substitute with the following:

Diaphragm-actuated pilot-control valves shall be constructed of the following:

TABLE 212-5.7.2

| Item | Material | Specification |
|---------------------------------------------------------------|----------------------------------------------------|-------------------------------------------------------|
| Main Valve Body and Cover, Disc Retainer and Diaphragm Washer | Ductile Iron (for pressures 0-300 psi) | ASTM A536 |
| Main Valve Trim: Stem, Seat and Bonnet Spring | SAE Type 316 Stainless Steel | ASTM A276 or A351 |
| Stem Guide Bearings, Upper and Lower | SAE Type 316 Stainless Steel | ASTM A276 |
| Disc | Buna-N Rubber or | |
| | EPDM for Reclaimed Water | |
| Diaphragm | Nylon-Reinforced Buna-N Rubber or | |
| | EPDM for Reclaimed Water | |
| Pilot Control System | Cast Bronze with SAE Type 316 Stainless Steel Trim | Lead free for potable water applications ASTM A276 |
| Piping and Tubing | SAE Type 316 Stainless Steel | |

212-6 HYDRANTS

212-6.1 Fire Hydrants.

212-6.1.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-6.1.1

TABLE 212-6.1.1

| Item | Manufacturer |
|----------------------------------------|---------------------------------|
| Wet Barrel Fire Hydrants (Residential) | Clow Valve Model F2050 |
| | James Jones Company Model J3710 |

(UPDATED: 07-21)

| | |
|------------------------------------------------------------------------------|-----------------------------------------------------------|
| Bronze 4" x 2½") | |
| Wet Barrel Fire Hydrants (Residential Cast Iron 4" x 2½") | Clow Valve Model F850 James Jones Company Model J4040B |
| Wet Barrel Fire Hydrants (Commercial Bronze 4" x 2½" x 2½") | Clow Valve Model F2060 James Jones Company Model J3765 |
| Wet Barrel Fire Hydrants (Commercial Cast Iron 4" x 2½" x 2½") | Clow Valve Model F860 James Jones Company Model J4060B |
| Wet Barrel Fire Hydrants (Commercial Bronze 4" x 4" x 2½" Double Steamer) | Clow Valve Model F2065 James Jones Company Model J3775 |
| Wet Barrel Fire Hydrants (Commercial Cast Iron 4" x 4" x 2½" Double Steamer) | Clow Valve Model F865 |

212-6.1.1 General.

Delete second sentence and substitute with the following:

Color scheme shall comply with City of Corona standards. If no such standards exist, hydrants shall be painted per Table 212-12.2.

212-7 BACKFLOW PREVENTION DEVICES.

212-7.2 Double Check (DC) Valve Backflow Prevention Assemblies.

Add the following:

Acceptable manufacturers and models are listed in the University of Southern California (USC) list of – Approved Backflow Prevention Devices available from the USC Foundation for Cross-Connection Control and Hydraulic Research. Backflow prevention assemblies must meet all lead-free requirements.

212-7.3 Reduced-Pressure (RP) Backflow Prevention Assemblies.

Add the following:

Acceptable manufacturers and models are listed in the University of Southern California (USC) list of – Approved Backflow Prevention Devices available from the USC Foundation for Cross-Connection Control and Hydraulic Research. Backflow prevention assemblies must meet all lead-free requirements.

212-8 COUPLINGS

212-8.1 Bolted Sleeve Type Couplings.

(UPDATED: 07-21)

212.8.1.1 General.*Add the following:*

Acceptable manufacturers are listed in Table 212-8.1.1.

TABLE 212-8.1.1

| Item | Manufacturer |
|-------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|
| Couplings – Steel Bolted Sleeve Type, for Identical Pipe Materials on each side | Dresser Piping Specialties (Style 38) |
| | Romac Industries (400) |
| | Smith Blair, Inc. (Style 411) |
| | Total Piping Solutions (Hymax) |
| Couplings – Steel Bolted Transition Sleeve Type, for Different Pipe Materials on each side | Dresser Piping Specialties (Style 162) or (Style 62TY.1) |
| | Romac Industries (TC400) |
| | Smith Blair, Inc. (Style 413) |
| | Total Piping Solutions (Hymax) |
| Couplings – Ductile Iron Bolted Sleeve Type System, for Identical or Different Pipe Materials on Each Side | Romac Industries (501) or (XR501) |
| | Smith Blair, Inc. (Style 461 Quantum) |
| Couplings – Ductile Iron Bolted Sleeve Extended Range Type for Identical or Different Pipe Materials on Each Side | Romac Industries (501) |
| | Smith Blair, Inc. (Style 462 Quantum) |

212-8.2 Flanged Coupling Adaptors**212-8.2.1. General.***Add the following:*

Acceptable manufacturers are listed in Table 212-8.2.1.

TABLE 212-8.2.1

| Item | Manufacturer |
|-----------------------------------------------------------|--------------------------------------------------------------------------|
| Couplings, Flanged Coupling Adaptor for Ductile Iron Pipe | Romac Industries (FCA 501) |
| | Smith Blair, Inc. (Style 912) 3"- 12" |
| | Smith Blair, Inc. (Style 913) 3"- 24" |
| Couplings, Flanged Coupling Adaptor (Restrained) | EBAA Iron Megaflange Series 2100 3"-24" |
| | Ford Meter Box Company (Restrained Flange Adaptor with UFR 1400) 3"- 24" |

(UPDATED: 07-21)

212-8.3 Coupling Restraint Systems.

Delete the following from Table 212.8.3:

TABLE 212-8.3

| Item | Material | Specification |
|------------------|--------------------|------------------------------------------------------------------------------------------|
| Tie Rods – Steel | Carbon Steel | ASTM A193 Grade B7 threaded rods. Do not use all-thread. |
| | Galvanized Coating | ASTM A123 – 3.4 mil (90 µm) thickness – 2.00 oz./ft ² (610 g/m ²) |

212-8.4 Grooved and Shouldered Couplings and Joints.**212-8.4.1 General.**

Add the following:

Acceptable manufacturers are listed in Table 212-8.4.1

TABLE 212-8.4.1

| Item | Manufacturer |
|-----------------------------------------------------------------|-------------------------------------------------------------|
| Couplings – Flexible Grooved Type for Steel Pipe 4” through 24” | Victaulic Company of America, Inc. (Style 77) |
| Couplings – Roll-Grooved Type for Steel Pipe 28” through 42” | Victaulic Company of America, Inc. (Style 770) |
| Couplings –Shouldered Type for Steel Pipe 4” through 60” | Victaulic Company of America, Inc. (Style 44 with Vic-Ring) |
| Couplings – Grooved Type for Ductile Iron Pipe 3 “ through 36” | Victaulic Company of America, Inc. (Style 31) |

212-9 EXPANSION JOINTS**212-9.1 Double-Ball Expansion Joints.****212.-9.1.1 General**

Add the following:

Acceptable manufacturers are listed in Table 212-9.1.1.

TABLE 212-9.1.1

(UPDATED: 07-21)

| Item | Manufacturer |
|--------------------------------------------------------------------------|---------------------------------------|
| Expansion Joints – Double-Ball Type with Telescoping Ductile Iron Sleeve | EBAA Iron (Flex-Tend) |
| Expansion Joints – Double Ball Type Force Balanced | EBAA Iron (Forced Balanced Flex-Tend) |

212-10 SERVICE LATERALS, METERS, AND METER BOXES

212-10.3 Corporation Stops, Angle Meter Valves, Service Saddles and Other Service Materials.

Add the following:

Acceptable manufacturers are listed in Table 212-10.3.

TABLE 212-10.3

| Item | Manufacturer |
|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| Angle Meter Stop (Ball Valve) | Ford Meter Box Co. BA43-444W-NL |
| | James Jones E-1963WSG or E-1975WSG |
| | Mueller Company B-24258N or B-24276N |
| | A.Y.McDonald Mfg. Co. 74602BQ or 74602BCSQ |
| Brass Body Type 304L Stainless Steel Double-Strap Service Saddles for AC, CIP, DIP, and PVC Pipe | Ford Meter Box Co. Style 202BSD and 202BS |
| | Mueller Company BR2S and BR2W Series |
| | James Jones J-969 and J-969W Series |
| | A.Y.McDonald Mfg. Co. 3825 and 3826 |
| Brass Body Flattened Bronze Double-Strap Service Saddles for DIP Only | Ford Meter Box Co. Style 202B |
| | Mueller Company BR2B Series |
| | James Jones J-979 Series |
| Corporation Stops | Ford Meter Box Co. FB1000-3-Q-NL, FB1000-4-Q-NL, FB1000-6-Q-NL, or FB1000-7-Q-NL |
| | James Jones E1935SG |
| | Mueller Company B-25028N |
| | A.Y. McDonald Mfg. Co. 74704BQ |
| Customer Service Meter Valves | Ford Meter Box Co. Style B13-344W-NL and B13-444W-NL with “lock off” handle |
| | James Jones Style E-1900W with “lock off” handle |
| | Mueller Company B24351N or B-20200N with “lock off” handle |
| | A.Y. McDonald Mfg. Co. 76101MW with “lock off” handle |
| Meter Bolts – Silicon Bronze | Tripac Fasteners |
| Meter Yokes | Ford Meter Box Co. |

(UPDATED: 07-21)

212-10.4 Meters.

Delete entire subsection and substitute with the following:

Acceptable types of meters shall be as shown on the Plans or Standard Plans.

Registers shall be straight-reading type, hermetically sealed, having a register test hand. Registration shall be in gallons or cubic feet as shown in the Special Provisions. Registration accuracy shall comply with AWWA or these Special Provisions. Meters 5/8-inch through 2-inch in size shall provide remote read capabilities for remote meter reading system. Meters larger than 2-inch size shall be installed in above-ground locations. Magnetic meters shall provide local read with 4-20mA signal output where required by City.

Acceptable manufacturers are listed in Table 212-10.4.1

TABLE 212-10.4.1

| Item | Manufacturer |
|-----------------------------------|-----------------------------|
| Positive Displacement Flow Meters | Neptune Model T-10 |
| Compound Flow Meters | Neptune Tru/Flow Compound |
| Magnetic Flow Meters | Endress + Hauser Promag 400 |

Meters shall conform to the following:

TABLE 212-10.4.2

| Type of Meter | Size Range | Case | Specification |
|------------------------------|---------------------|------------------------------|---------------------------------------------------------------------------|
| Positive Displacement Meters | 5/8" through 1-1/2" | Lead Free High Copper Alloy | Accuracy to 1.5% within normal operating flow range – remote read capable |
| Compound Meters | 2" | Lead Free High Copper Alloy | Accuracy to 1.5% within normal operating flow range – remote read capable |
| Compound Meters | 3" through 8" | Lead Free High Copper Alloy | Accuracy to 1.5% within normal operating flow range |
| Magnetic Meters | 4" through 54" | Epoxy-Lined and Coated Steel | Accuracy to 0.5% within flow range having 20:1 minimum turndown ratio |

212-10.6 Meter Boxes.

Delete entire subsection and substitute with the following:

212-10.6.1 General.

Meter boxes and lids in parkways and areas not subject to traffic shall be polymer. Meter boxes and lids subject to traffic shall be concrete, H-20 traffic load rated. Provide remote read lid labeled "WATER".

Acceptable manufacturers are listed in Table 212-10.6.1.

TABLE 212-10.6.1

| Item | Manufacturer |
|-------------------------------------------------------------------|------------------------------------------------------|
| Meter Box for 1" Meter and Smaller without Fire Sprinkler Service | DFW Plastic Inc. DFWPW6C4-12-4F (16-5/16" x 31-3/4") |
| Meter Box for 1" Meter and Smaller with Fire Sprinkler Service | DFW Plastic Inc. DFWPW6C4-12-4F (16-5/16" x 31-3/4") |
| Meter Box for 1½" Meter and 2" Meter | DFW Plastic Inc. DFWPW6C4-12-4F (16-5/16" x 31-3/4") |
| H-20 Load Rated Concrete Meter Box for 2" Meter and Smaller | DFW Plastic Inc. DFWPW6C4-12-4F (16-5/16" x 31-3/4") |

212-10.6.2 Dimensions.

Minimum meter box dimensions shall conform to the following:

TABLE 212-10.6.2

| Size of Meter | Interior Length (Below Lip) | Interior Width (Below Lip) | Depth |
|----------------------|------------------------------------|-----------------------------------|--------------|
| ¾" or less | 25" | 13" | 12" |
| 1" | 25" | 13" | 12" |
| 1½" | 29" | 16" | 12" |
| 2" | 29" | 16" | 12" |

212-11 PRESSURE GAUGES**212-11.1 Stem-Mounted Pressure Gauges.****212.-11.1.1 General.**

Add the following:

Acceptable manufacturers are listed in Table 212-11.1.

TABLE 212-11.1.1

| Item | Manufacturer |
|--------------------------------|---------------------------------|
| Pressure Gauges – Stem-Mounted | Ashcroft Type 1008S (0-300 psi) |
| | U.S. Gauge Company (Ametek) |

(UPDATED: 07-21)

| | |
|-------------------|--------------------------------------------|
| Bourdon Tube Type | Wika Instrument Corporation Div Ryan Herco |
|-------------------|--------------------------------------------|

212-11.1.2 Materials.

Delete the following from Table 212.11.1.2:

TABLE 212-11.1.2

| Item | Material | Specification |
|------|----------|---------------|
| Case | ABS | |

Delete and substitute the following in Table 212.11.1.2:

TABLE 212-11.1.2

| Item | Material | Specification |
|--------|--------------------------|---------------|
| Window | Polycarbonate Acrylic | |

212-11.1.3 Design Options.

Delete and substitute the following in Table 212.11.1.3:

TABLE 212-11.1.3

| Item | Option | Specification |
|------|---------------------------|-----------------------------------------------------------------------------------------------------------------------------------|
| Dial | Calibrated Pressure Range | 0-200 psi unless otherwise shown on plans or operating pressure exceeds 175 psi. 0-300 psi if operating pressure exceeds 175 psi. |

212-11.2 Flanged In-Line Sensor Sleeve Style Pressure Gauges

212-11.2.1 General.

Delete first sentence and substitute with the following:

Flanged in-line sensor sleeve style pressure gauges shall be used in wastewater applications.

Add the following:

Acceptable manufacturers are listed in Table 212-11.2.1.

TABLE 212-11.2.1

| Item | Manufacturer |
|-------------------------------------------|----------------------|
| Pressure Sensors and Gauges – Flanged in- | Cla-Val Company CVPS |
| | Onyx Valve |

(UPDATED: 07-21)

| | |
|--------------------------|-------------------------------|
| line Sensor Sleeve Style | Red Valve Company (Series 40) |
|--------------------------|-------------------------------|

212-12 PAINTING, INTERIOR LINING, AND EXTERIOR COATING.

212-12.1 Lining and Coating of Ferrous Valve, Hydrant, Valve Operator, Meter, Coupling, Expansion Joint, Spool, Fitting, and Backflow Preventer Surfaces.

212-12.1.1 General.

Add the following:

Acceptable manufacturers are listed in Table 212-12.1.1.

TABLE 212-12.1.1

| Item | Manufacturer |
|--------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| NSF-Approved Fusion-Bonded Epoxy Linings and Coatings | 3M Scotchkote 134, 206N or 6233 |
| | Northtown Keysite 740 |
| Fusion-Bonded Epoxy Linings and Coatings (Not NSF 61-Listed) | 3M Scotchkote 134, 135, 203, 206, 206-N or 6233 |
| | Gilpon |
| | Northtown Keysite 740 |
| Field-Applied Liquid Epoxy Linings and Coatings for Patching | Valspar "Pipe Clad" 1500 Red |
| | 3M Scotchkote 306 |
| Field-Applied Liquid Epoxy Linings and Coatings for Patching Welded Steel Pipe | 3M Scotchkote 302 |
| NSF-Approved Liquid Epoxy Linings and Coatings | 3M Scotchkote 323 |
| | ICI Devoe - Sinclair - ICI Dulux Paint Div. Glidden Co. Bar Rust 233 series |
| | Tnemec Pota-Pox L140 |
| Liquid Epoxy Linings and Coatings | 3M Scotchkote 312 or 314 |
| | ICI Devoe - Sinclair - ICI Dulux Paint Div. Glidden Co. Bar Rust 233 series |
| | Tnemec Pota-Pox L140 (For nonpotable water use Tnemec Series L69) |
| Polyethylene Encasement for Corrosion Protection | Christy's "AWWA Polywrap" |
| | Dupont Alathon |
| | Northtown Company |
| | Trumbull Industries, Inc. |
| Tape for Polyethylene Encasement | Berry Plastics "Polyken No 900" |
| | Plicoflex No 340 |
| | Protecto Wrap No 200 |
| | Scotchwrap (3M), No 50 |

(UPDATED: 07-21)

SECTION 306 – OPEN TRENCH CONDUIT CONSTRUCTION

SECTION 306-1.5.2 Permanent Resurfacing

Add the following after the last paragraph:

Limits of AC overlay shall extend to edge of pavement or nearest lane line with a 2-foot minimum taper.

Disturbing more than one lane requires an overlay over the width of all lanes affected by the Work. For two-lane roadways, the requirement will be from centerline to edge of pavement overlay.

306-2 DELIVERY, STORAGE, HANDLING AND PROTECTION OF PIPELINE MATERIALS, FITTINGS, VALVES, AND APPURTENANCES.

306-2.2 Shipment and Delivery.

306-2.2.1 General.

Add the following:

- a) Only new pipeline products of accepted manufacturers shall be delivered to or used on the site.
- b) Contractor shall not ship, accept delivery of, or store manufactured items on site for which applicable submittals have not been approved.
- c) Before shipping, the pipe, valves, motors, actuators and mechanical equipment shall be operated and tested at the factory to ensure products are complete and in working condition. Submit certified test results.
- d) Within one working day following pipe delivery, remove the pipe end covers, swab the entire pipe interior with a bleach solution, replace pipe end covers, and securely wrap the plastic and tape. Retain pipe end covers and plastic wrap covering on pipe until pipe is installed in trench.

306-2.3 Storage.

Add the following:

- m) No pipe or materials shall be left along right-of-way overnight.

Pipe or materials may be allowed to be left along right-of-way overnight outside of traveled area and behind curb and gutter or edge of pavement with preapproved City written authorization. Contractor shall be responsible for his own protection against theft or vandalism and shall demonstrate that the overnight stringing of pipe or materials will not be a hazard to the public.

306-2.5 Protection of Pipe Interiors.

Delete first sentence of the second paragraph and substitute with the following:

Cover with rubber, plastic, or canvas during shipping, storage, and staging for installation pressure pipe and clean water gravity pipe, pipe ends, fitting ends, valve ends, and equipment openings to prevent intrusion or contamination. Pipes and fittings without openings covered will not be accepted for delivery.

306-2.7 Shutdowns of Existing Pipelines.

306-2.7.1 General.

Delete entire subsection and substitute with the following:

Work requiring the shut-down of an existing pipeline for the Contractor's benefit shall be performed by forces employed by the City of Corona or affected utility if not City-owned. Under no circumstances shall the Contractor operate valves, hydrants or other appurtenant equipment on existing public utilities.

The City, or utility owner, will make a concerted effort to isolate pressure pipelines as planned. However, the Contractor shall be prepared to employ pumping and dewatering equipment if a watertight seal cannot be achieved by City or utility forces. The Agency will not be responsible for any delays or expenses due to difficulties with system shutdown and isolation.

All emergency situations shall be reported immediately to the affected utility.

306-2.7.3 Temporary Bypass.

Delete entire subsection and substitute with the following:

Where main shutdowns in excess of 4 hours are required, the City, or affected utility, will determine what temporary bypasses or service connections may be required. The Contractor shall furnish all necessary hose, piping, valves, water trucks, disinfection, and labor to provide and maintain temporary service. All piping, hoses and associated equipment used for temporary potable water service shall be flushed and disinfected in accordance with 306-8.9.4.

306-8 PREFABRICATED PRESSURE PIPE.

306-8.1 General.

Add the following:

Unless otherwise shown, water pipe, fittings, and appurtenances used in the City of Corona shall be fully self-restrained ductile iron pipe. PVC pressure pipe shall not be used in the City of Corona.

Except for short runs, sections of pipe shall be installed in a sequence moving in an upgrade direction on grades exceeding 10 percent. Pipe installed in a downgrade direction shall be secured to prevent movement.

Closure and correction pieces shall be provided as required to adjust the pipe installation to conform to the pipe alignment and stationing shown.

Pipe will be inspected in the field before and after installation. Pipe which is not in true alignment or shows any undue settlement after installation shall be removed and re-installed. If any cause for rejection is discovered in a pipe after it has been installed, it shall be subject to

(UPDATED: 07-21)

rejection. Corrective work shall be approved by the Engineer.

306-8.2 Ductile Iron Pipe

306-8.2.2.1 Push-on Joints.

Delete the sentence describing the use of flex-ring, split-ring, or ring segments restraint and substitute with the following:

Push-on restrained joints shall incorporate locking gasket type restraint and shall be installed in accordance with the manufacturer's installation and warranty instructions for the joint design used.

306-8.2.2.3 Installation of Polyethylene (PE) Film Wrap on Iron Fittings.

Delete paragraph c) and substitute with the following:

- c) Film wrap shall not be installed on pipe sections or fittings to be concrete encased, installed within casing, or installed through concrete slope anchors.

306-8.8.2.1 General.

Add the following:

Valves and appurtenances shall be constructed in accordance with the City of Corona Standard Plans.

306-8.8.4 Service Connections.

Delete entire subsection and substitute with the following:

Service connections shall be constructed as shown on the Plans and in accordance with the City of Corona Standard Plans. Minimum service connection size shall be 1 inch. Where mains are laid in paved streets, service connections 2 inches and smaller shall be installed by boring rather than by cutting the pavement unless prior written approval from the Engineer is obtained to avoid conflict with other utilities.

Service laterals shall be placed under curbs and gutters by boring rather than by open trenching. The letter "W" shall be inscribed in the center of the curb face in line with each meter installation. The "W" shall be approximately 1½ inches high and 1/16 inch deep. No kinks, flats, crushes or other reductions in the diameter of service laterals will be permitted.

Add the following:

306-8.8.6 Fire Hydrant Installation.

Fire hydrants shall be constructed in accordance with the City of Corona Standard Plans. The hydrant lateral shall be flushed through each fire hydrant with a City of Corona Fire Department Representative present to test for maximum fire flow capabilities. The Contractor shall notify the Fire Department 72 hours in advance of such test.

306-8.9 Hydrostatic Pressure Test.

(UPDATED: 07-21)

Delete entire heading and substitute with the following:

306-8.9 Hydrostatic Pressure Test and Flushing.

306-8.9.2.2 Preparation.

Add the following after the first paragraph:

Four-hour hydrostatic pressure test shall proceed prior to placing permanent surfacing, but after the following have occurred:

- a) Pipe appurtenances and permanent thrust blocks shall be installed and backfilled sufficiently to provide the required bearing area.
- b) Trench backfill involving compactive effort using heavy-duty compacting equipment weighing more than 100 pounds shall be completed.
- c) Thrust blocks and other field-placed concrete and mortar in contact with the pipe shall have been in place and allowed to cure for at least 7 days.
- d) Valves shall be verified by the Contractor to be bubble-tight and closed where available.
- e) Butterfly valves or other valves having a working pressure rating less than the test pressure shall be braced and blocked by the Contractor to provide a minimum back-pressure on these devices equal to the difference between the test pressure the valve or device's rated working pressure.
- f) Temporary bulkheads shall be placed in the pipe where valves are not available.
- g) Air test gauges shall be laboratory calibrated no more than one year prior to test.
- h) Contractor shall make arrangements to meter, pay for, deliver and dispose of test water.
- i) At least 24 hours before the test the pipeline shall be filled slowly with the air vents open and maintained at operating pressure for at least 24 hours to satisfy any system water absorption.
- j) Air shall be expelled from the pipeline to the best of the Contractor's ability.
- k) Bulkheads, valves, and connections shall be examined for leaks and corrective measures shall be taken to eliminate any leaks discovered.
- l) The Engineer shall be present to verify testing and record results.
- m) The Engineer shall be allowed to verify all intermediate valves are in the open position so "short-sheeting" cannot occur during pressure testing.

Test pressure shall be 200 psi as measured at the highest elevation of the water main under test.

Delete the entire second, third and fourth paragraphs and add the following sections:

306-8.9.2.2.1 Initial Flushing.

The Contractor shall flush all potable water mains and services with potable water to flush out debris prior to disinfection in accordance with the City provided flushing plan. Nonpotable water may be used for flushing of nonpotable water mains and services.

Work includes providing, installing and removing fittings, connectors, manifolds, piping, hoses, adapters, and construction water meter and backflow prevention device required to

(UPDATED: 07-21)

provide source water as necessary to flush mains and services to achieve the required minimum flushing velocity over the entire length of the pipe as tabulated below.

| PIPE DIAMETER | REQUIRED FLUSHING VELOCITY | REQUIRED FLUSHING FLOW | NUMBER OF SOURCE HYDRANTS REQUIRED | MINIMUM SIZE SUPPLY FITTING | MINIMUM SIZE SUPPLY HOSE OR PIPE | MINIMUM SIZE DRAIN FITTING | MINIMUM SIZE DRAIN HOSE OR PIPE |
|---------------|----------------------------|------------------------|------------------------------------|-----------------------------|----------------------------------|----------------------------|---------------------------------|
| 6-inch | 5 FPS | 440 gpm | 1 | 4-inch | 4-inch | 4-inch | 4-inch |
| 8-inch | 5 FPS | 790 gpm | 1 | 4-inch | 4-inch | 4-inch | 4-inch |
| 10-inch | 5 FPS | 1,223 gpm | 1 | 6-inch | 6-inch | 6-inch | 6-inch |
| 12-inch | 5 FPS | 1,762 gpm | 2 | 8-inch | 6-inch | 8-inch | 8-inch |
| 16-inch | 3 FPS | 1,870 gpm | 2 | 8-inch | 6-inch | 8-inch | 8-inch |
| 20-inch | 3 FPS | 2,936 gpm | 3 | 10-inch | 6-inch | 10-inch | 10-inch |
| 24-inch | 2.5 FPS | 3,523 gpm | 3 | 12-inch | 6-inch | 12-inch | 12-inch |
| 30-inch | 2.5 FPS | 5,505 gpm | 4 | 12-inch | 6-inch | 12-inch | 12-inch |

Remove fire hydrant head and install flanged tee at supply source for flushing all water mains larger than 8-inch diameter.

The backflow device and metered connection to the potable supply will be sized to meet this minimum flow requirement. Supporting calculations shall be submitted with the disinfection, testing, flushing and dechlorination plan. Velocities through outlets and fittings shall not exceed 25 feet per second (7.5 m/s) during flushing.

All pipelines shall be flushed for sufficient time to achieve 3 exchanges of the total volume of the pipeline as a minimum and until the flushing water exits the pipe in a clear condition having not more than 2 NTU turbidity as measured with a potable turbidity meter and not more than 0.5 mg/L suspended solids as measured in an eimhoff cone at all outlets.

Drainage facilities shall be constructed as necessary to ensure water lines do not become contaminated during flushing. The Contractor shall secure and adhere to the NPDES permit. If the Contractor is allowed to operate under the City's De Minimis Discharge permit, the Contractor will be charged for the hours necessary to supervise the preparation of lagoons, sampling, and laboratory analysis necessary to ensure compliance. The Contractor shall bear all direct and indirect costs.

Test or flushing water may be discharged to sanitary sewer system rather than discharging to storm drain, provided Contractor obtains and submits to Engineer a copy of written permission to discharge from sanitary sewer owner including supplementary information described above under Submittals. Schedule discharges to sewers during off-peak periods as recommended by sewer owner.

No entity or agent other than City of Corona DWP staff shall operate any valve or facility of the approved distribution system without the written consent and direct supervision of the DWP Chief Water Operator or designated representative.

Upon satisfactory test completion, permanently cap or plug any outlets used for flushing, testing or air release.

Unless otherwise specified, the Contactor shall make the arrangements for, and provide the water for, flushing and its subsequent discharge.

306-8.9.2.4 Test Procedure.

Add the following after the second paragraph:

(UPDATED: 07-21)

The test pressure for sewage force mains and pressure sanitary sewers shall be 120% of the maximum working pressure shown on Plans unless the test pressure is specified elsewhere in the Contract Documents.

Add the following after the ninth paragraph:

When leakage exceeds the amount allowed by the Specifications, the Contractor shall locate the leaks and make the necessary repairs or replacements in accordance with the Specifications to reduce the leakage or infiltration to the specified limits. Individual detectable leaks shall be repaired, regardless of the results of the tests.

306-8.9.4 Disinfection.

306-8.9.4.1 General.

Add the following:

Where the City's standard is more stringent than the associated AWWA standards, the City's standard shall supersede the AWWA standard.

Disinfection operations shall be scheduled by the Contractor as late as possible during the Contract time period to assure the maximum degree of sterility of the facilities at the time the Work is accepted by the City.

306-8.9.4.2 Submittals.

Delete "If requested by the Engineer" from the first section of Table 306-8.9.4.2 under the "Description" column.

306-8.9.4.3 Potable Water System Disinfection Procedures.

Delete entire section and substitute with the following:

All potable water pipelines except those appurtenant to hydraulic structures shall be disinfected in accordance with the requirements of AWWA C651 using the Continuous-Feed Method as modified herein. The Contractor shall provide sampling locations in accordance with AWWA C651, the California Department of Public Health Safe Drinking Water Systems regulations, and requirements herein.

Preliminary and final flushing shall be performed on mains, which have been hydrostatically tested in accordance with the flushing plan.

Disinfection shall not be combined with any other activity such as pressure testing or flushing. Disinfection shall be against a capped or plugged line. The new main will be accepted as a whole and not in portions as they pass inspection. The only exception will be for very large projects where physical separations are used at predetermined locations and the procedures are clearly detailed in the pre-approval plan.

Contractor shall not allow chlorinated water to remain in contact with internal waterway ports of pumps, valves, and sensor line assemblies for longer than required to perform disinfection process.

All chemicals for chlorination and temporary valves, temporary blow-offs, bulkheads, backflow devices to prevent the strong chlorine solution in the line being disinfected from backflowing into the line supplying the water, or other necessary devices, chemicals or and

(UPDATED: 07-21)

materials shall be furnished by the Contractor. No materials shall be used which would be injurious to the pipeline or its future function. Contractor shall keep adequate chlorine residual testing and indicating apparatus available on site during the entire disinfection period.

Unless otherwise indicated, potable water for testing and disinfecting water pipelines shall be furnished by the Contractor. Contractor shall also make all necessary arrangements for conveying the water to the points of use.

Chlorine for disinfection shall be in the form of sodium hypochlorite solution. The use of chlorine gas is not allowed. Sodium hypochlorite solution shall be used only:

- a) Under the direct supervision of an experienced technician;
- b) When all safety practices are observed.

Disinfection shall be accomplished by chlorination. Chlorinating and testing operations shall be performed in the presence of the City's Representative.

A chlorine-water mixture shall be uniformly introduced into the pipeline by means of a solution-feed chlorinating device. The chlorine solution shall be introduced at one end of the pipeline through a tap in such a manner that as the pipeline is filled with water, the dosage produced in all sections of the pipelines and appurtenances shall be not less than 50 mg/l nor more than 100 mg/l. Contractor shall make 24-hour chlorine residual tests and notify the Engineer of all chlorine test results.

Chlorinated water shall be retained in the pipeline for at least 24 hours. After the chlorine-treated water has been retained for the required time, the free chlorine residual at the pipeline extremities and at other representative points shall be at least 50 mg/l free chlorine. If the tests are not satisfactory, the Contractor shall provide additional disinfection as required until all tests are passed.

Placing of HTH capsules or powder in pipe sections during the laying process will not be considered adequate disinfection. The Contractor shall keep adequate chlorine residual testing and indicating apparatus available on site during the entire disinfection period. After final flushing, Contractor shall plug flushing fittings with devices intended for this purpose at pressure class of pipe. Where water main is coated for disinfection, plugs and outlets shall be similarly coated.

Contractor shall keep and provide accurate documentation of dosing rate (ppm), time of dosing and duration. Dosing agent's name, contact information and signature shall be provided.

Disinfection testing procedure shall be repeated if the initial tests fail to produce satisfactory results. Two consecutive satisfactory test results shall be required after any unsatisfactory test. The tablet method shall not be used for repeated disinfection.

During disinfection, all valves, hydrants, and other accessories shall be operated. All appurtenances shall be disinfected. Pipe and appurtenances used to connect the newly installed water main shall also be disinfected in accordance with AWWA C651.

306-8.9.4.5 Dechlorination and Flushing.

Add the following after the first paragraph:

Final Flushing shall be done by the Contractor after satisfactory chlorine residual test results have been returned and accepted by the Engineer.

Dechlorinate and remove pollutants from water flushed from water mains where discharging or draining to gutters, streets, storm drains, or any constructed or natural drainage channels (waters of the State) in accordance with AWWA C655 and NPDES Permit applicable for pipeline flushing.

Water flushed from water mains and spread on-site with no runoff does not require

(UPDATED: 07-21)

dechlorination.

Flushing water may be discharged to sanitary sewer system as alternative to discharging to storm drain, provided Contractor obtains and submits to City a copy of written permission to discharge from sanitary sewer owner including supplementary information described above under Submittals. Schedule discharges to sewers during off-peak periods as recommended by sewer owner.

After the applicable retention period, the heavily chlorinated water shall be flushed from the pipeline at its extremities until chlorine measurements show the concentration in the water leaving the pipeline is equal chemically and bacteriologically to those of permanent source of supply. A reducing agent shall be applied to the water to neutralize thoroughly the chlorine residual remaining in the water in accordance with AWWA C655 and the NPDES Permit applicable for the Water Quality Region in which the discharge occurs.

The following are parameters for flushing after disinfection:

- a) High chlorine concentration (super-chlorinated) water will be flushed completely from the main and discharged in compliance with the requirements of the NPDES general permit.
- b) The NPDES general discharge permit requires neutralization of the chlorine before it contacts the "waters of the State." How this will be achieved shall also be covered in the approved flushing and disinfection plan. A field test kit shall be used to adjust the neutralization. Samples shall be collected and analyzed by the colorimetric method to demonstrate the effectiveness of the neutralization.
- c) The NPDES general discharge permit (Table E-1) lists the discharge event parameters requiring monitoring for discharge of super-chlorinated water.
- d) The NPDES general discharge permit (Table E-2) requires one sample collected for discharge durations less than 20 minutes, and one sample during the first 10 minutes and a second sample within the last 10 minutes for flushing durations between 20 minutes and 60 minutes.
- e) All discharges must be <0.10mg/L Total Cl₂ residual.
- f) Total chlorine residual will be measured in the source water. A field test kit that measures total and free chlorine and is approved for potable water reporting purposes shall be used. Pool kits are not acceptable. When the same total chlorine residual as measured in the source water is detected at all outlets and no free chlorine is present, then the flushing is complete.

306-8.9.4.6 Bacteriological Sampling and Testing.

Delete entire section and substitute with the following:

Provide not less than 5 business days advance notification to the City of all sampling activities to include proposed sampling location, description of sampling point, and name of firm or individual who will perform sampling. Provide sketch or plan showing the proposed sampling locations in accordance with AWWA C651, the California Department of Public Health Safe Drinking Water Systems regulations, and requirements herein. A City-provided flushing and disinfection plan may be used to meet this requirement to the extent the flushing and disinfection plans shows proposed sampling locations.

Sampling shall be accomplished by a qualified sampler employed by a certified laboratory. Laboratory certification shall be evidenced in the approved plan.

The qualified sampler employed by a certified laboratory shall collect a minimum of 2 sets of samples on consecutive days not less than 16 hours nor more than 24 hours apart after

(UPDATED: 07-21)

completion of final flushing. Deliver bacteriological samples to a certified laboratory for bacteriological testing.

No flushing or any movement of water in the pipe is allowed during sampling phase.

Provide legible chain of custody documentation from point of sampling to laboratory for each sampling location. Do not commingle samples from different projects or different parts of the same project on the chain of custody or testing report.

Locations for water sampling for bacteriologic testing shall follow the requirements of AWWA C651 and shall be taken from each end of the disinfected main (located downstream of point of introduction of chlorine disinfectant), all branches of the new main, at intermediate points at intervals no greater than 300-feet, and at the downstream side of the backflow preventer at the flushing supply. The chain of custody shall describe this sample point as "Backflow". Sample points shall conform to those submitted in the approved disinfection plan. A second set of samples shall be collected from the same sample points as the first samples, without exception, not less than 16 hours nor more than 24 hours after the first set of samples were collected. Test results showing different numbers of samples or different locations of sample points shall be cause for rejection of the bacti results.

Temperature, total chlorine and free chlorine residuals shall be measured with a field test kit and recorded by the sampler on the "chain of custody" form. Both sample sets shall be analyzed for total and fecal coliform presence/absence and heterotrophic plate count. The Contractor may choose to request resample to verify or discredit laboratory results when one or two of many are unsatisfactory and a sampling error is suspected. The City of Corona reserves the right to sample for bacteria at its own discretion with notice.

Source water shall also be sampled two weeks prior to sampling and bacteriological testing, or the nearest water quality sample station's most recent results shall be used to determine the baseline water quality for the duration of the project. Source water sampling shall be under the supervision of the City's Water Production and Distribution Division staff.

Testing procedures shall follow the current edition of the Standard Methods for the Examination of Water and Wastewater. Satisfactory bacteriological results shall be as follows:

- a) No total or fecal coliform,
- b) heterotrophic plate count less than 500CFU and
- c) Cl₂ residual shall be no less than 50 percent of the source water

Passing bacteriological tests on two consecutive days shall be achieved prior to placing the pipeline into service. In the event disinfection fails to produce satisfactory results in total or fecal coliform, the pipe shall be re-flushed, re-disinfected, resampled, and retested. In the event disinfection fails to produce satisfactory results in only heterotrophic plate count, the pipe may be re-flushed, resampled and retested one time at the City's discretion with City's written approval. If results from analysis of the second samples exceed the above criteria, the pipe shall be re-flushed, re-disinfected, resampled and retested until satisfactory results are obtained. All sampling and laboratory testing shall be at Contractor's expense. The Contractor shall be responsible for all repeat bacteriological testing costs.

306-8.9.5 Pipeline Commissioning.

Delete entire section and substitute with the following:

Pipeline shall be placed into service as soon as practical and within seven (7) calendar days following receipt of passing bacteriological test results. Failure to place the pipeline into service within the time limit stipulated will require the Contractor to reflush, resample, and retest the pipeline at the Contractor's cost prior to placing pipeline into service. Provide not less than 3

(UPDATED: 07-21)

business days advance notification to the City for all pipeline connections to enable City to provide engineering and field support. Connections shall be performed only on Tuesdays, Wednesdays, or Thursdays.

306-12 BACKFILL

306-12.4 Jetted Trench Backfill

306-12.4.1 General.

Add the following:

Jetting of backfill shall not be permitted for potable water main construction.