



WEST 2ND APARTMENTS

APN: 118-270-053 & 118-270-055

PRELIMINARY DRAINAGE ANALYSIS

Prepared for:

C&C DEVELOPMENT CO., LLC

14211 YORBA STREET, SUITE 200

TUSTIN, CA 92780

Prepared by:

SHELBY SHIRLOCK, P.E.

Date Prepared: APRIL, 2024

Project Number: [1339-010&011]

FUSCOE ENGINEERING, INC.

600 Wilshire Blvd, Suite 1470 Los Angeles, California 90017

fuscoe.com





Date Prepared: April 2024

PRELIMINARY DRAINAGE REPORT

CORONA 2ND STREET APARTMENT

CORONA, CA - COUNTY OF RIVERSIDE

Date Prepared: April 2024

1339.010&011

PRELIMINARY DRAINAGE REPORT

CORONA 2ND STREET APARTMENT

CORONA, CA - COUNTY OF RIVERSIDE

Date Prepared: April 2024



1339.010&011

PRELIMINARY HYDROLOGY ANALYSIS

FOR

West 2nd Apartment & PSH

206 S. Buena Vista Avenue, Corona, CA County of Riverside

Prepared By:



Shelby Shirlock, PE Fuscoe Engineering, Irvine 600 Wilshire Blvd. #1470 Los Angeles, CA 90017 RCE C75912

For

C&C DEVELOPMENT 14211 Yorba Street, Suite 200 Tustin, CA 92780

TABLE OF CONTENTS

1.0	INTRO	DUCTION	2
1.1	GEO	Graphic Setting	2
1.2	PURP	OSE OF THIS REPORT	2
1.3	METH	ODOLOGY	2
1.4	PROJI	ECT SITE LOCATION MAP	3
2.0	EXISTIN	NG TOPOGRAPHIC & HYDROLOGIC CONDITIONS	4
2.1	EXISTI	NG TOPOGRAPHY	4
2.2	EXISTI	ng drainage pattern and storm drain facilities	4
3.0	PROPO	DSED PROJECT & HYDROLOGIC CONDITIONS	5
3.1	PROP	OSED PROJECT	5
3.2	PROP	OSED DRAINAGE PATTERN AND STORM DRAIN FACILITIES	5
4.0	STREET	CAPACITY ANALYSIS	7
5.0	DESIG	n Criteria	8
6.0	RESULT	TS AND CONCLUSIONS	9
7.0	APPEN	DICES	12
APPE		SUPPORTING MAPS AND PLANS	
APPE	NDIX 2	HYDROLOGY MAPS	12
APPE	NDIX 3	EXISTING HYDROLOGY CALCULATIONS	12
APPE	NDIX 4	PROPOSED HYDROLOGY CALCULATIONS	12
APPF	NDIX 5	PONDING EXHIBIT & STREET CAPACITY CROSS SECTIONS	12

1.0 INTRODUCTION

1.1 GEOGRAPHIC SETTING

The existing project site for the West 2^{nd} Apartment project consist of 4.18 acres and located in the City of Corona, Riverside County, California. The project site is located south 91 freeway, west of Buena Vista, east of Lincoln Avenue, and north of 6^{th} street. The project site is bounded by commercial property to the west and bounded by commercial and Orange Grove High School to the south and bounded by 2^{nd} Street to the north and bounded by Buena Vista Avenue to the east. See Section 1.4 for Location Map.

The project site is located at FEMA flood zone 'X' per FEMA Flood Insurance Rate Map (FIRM) No. 06065C0689G, map revised August 28, 2008. Flood Zone 'X' represents areas of minimum flood hazard (See Appendix 1).

1.2 PURPOSE OF THIS REPORT

The purpose of this report is to identify and analyze the existing drainage conditions & post development impacts, in order to provide adequate drainage facilities for the proposed development located in the City of Corona, California.


This drainage study will analyze and compare the 10-year & 100-year storm events for the existing and proposed conditions. Outcomes of the analysis will facilitate the conceptual layout of a drainage system to adequately convey storm runoff through the site without adversely impacting surrounding areas.

This analysis will also demonstrate that the storm water and flood protection goals as outlined in the Riverside County Design Manual have been met. See Section 5.0 for Design Criteria.

1.3 METHODOLOGY

This study was prepared in conformance with the Riverside County Hydrology Manual. A.E.S. Computer Software (Version 21) was utilized to compile the hydrologic data and to determine the peak discharges.

1.4 PROJECT SITE LOCATION MAP



The Project Site is identified in the location map shown below.

2.0 EXISTING TOPOGRAPHIC & HYDROLOGIC CONDITIONS

2.1 EXISTING TOPOGRAPHY

The approximate 4.18-acre project site area is vacant land consisting of vegetation, trees, and dirt. Most of the existing site is pervious. However, the project site was a former mobile home park until 2014. Therefore, the existing runoff coefficient was analyzed with the mobile home park factor.

The site's hydrologic soil group is 'B' per USDA Soil Map (See Appendix 7.1)

2.2 EXISTING DRAINAGE PATTERN AND STORM DRAIN FACILITIES

The existing site is currently divided into 3 drainage areas (A, B, and C)

Drainage area A, which is 0.72 acres of the site, is broken into 2 subareas that consists of existing dirt and wall (A1.1 and A1.2). The area drains along a 6-to-7-foot grade difference from southwest to northeast. Area A runoff is discharged to existing 2nd street.

Drainage area B, which is 2.75 acres of the site, is broken into 4 subareas that consists of existing dirt and wall (B1.1, B1.2, B2.1, and B2.2). The area drains along about 10-foot grade difference from southwest to northeast. Area B runoff is discharged to existing 2^{nd} Street.

Drainage area C, which is 0.71 acres of the site, consists of existing dirt and wall. The area has 7-foot grade difference from southwest to northeast an over 250' travel length. This area drains towards the Buena Vista.

All existing Drainage area A, B, and C onsite runoff joins Buena Vista and 2nd Street runoff and conveyed northerly via traditional cross gutter, and curb and gutters. This runoff is captured by a catch basin at northwest corner of Buena Vista and 2nd Street intersection. However, this catch basin directs the flow to the existing 54" RCP (Reinforced Concrete Pipe) Buena Vista storm drain which runs from south to north. This storm drain is noted in the city Drainage Master Plan to be deficient for this reach.

Refer to Appendices 7.2 and 7.3 for Existing Improvements, Hydrology Map and Calculations.

3.0 PROPOSED PROJECT & HYDROLOGIC CONDITIONS

3.1 PROPOSED PROJECT

The proposed project consists of 4 buildings in Family apartment parcel (3.46 AC) and 1 building in Permanent supportive housing parcel (0.72 AC) with paved parking lots, pool, and basketball court. The proposed project will be mostly impervious with some landscaped areas and will have project BMP's to mitigate the stormwater runoff.

3.2 PROPOSED DRAINAGE PATTERN AND STORM DRAIN FACILITIES

The proposed development will maintain the historic discharge point. Generally, onsite stormwater runoff will be captured by localized catch basins and drain inlets, and flows will be diverted into high and low flows. The low flows will be routed first to treatment points with Modular Wetlands Systems (MWS) to treat the proposed runoff. Once the runoff is treated by the MWS, the low water quality flows will be discharged into the existing underground 54-inch storm drain in Buena Vista. The 10-Yr (high) flows will be directed to a separate high flow storm drain pipe system and eventually to be discharged onto the streets via parkway culverts.

There are essentially three proposed drainage management areas delineated for the site.

Drainage Area A which is consists of the permanent supportive housing parcel apartment structure, parking lot, and landscape areas. Runoff will be conveyed via ribbon gutter and captured in catch basins that lead to an MWS system located at the northeast entrance. Runoff from the system discharges to 2nd Street through a proposed curb outlet.

Drainage Area B1 consists of the west side of building 1, landscape, and parking lot areas. Runoff will be conveyed via ribbon gutter and captured in a trench drain. The trench drain will have a low-flow outlet that leads to an MWS system located in the middle west of the parking lot. High flow will be diverted into a junction structure next to the trench drain. This junction structure connects to a curb outlet that discharges into the curb and gutter at 2nd Street.

Drainage Area B2.1, B2.2, and B3, consists of the majority of the northeast building 2, a minor portion of the northwest building 3, landscape, and pedestrian walkway. Runoff will be conveyed via swale and captured into open grate diversion structure at northeast corner of the project site. The diversion structure will have a low flow outlet that leads to a MWS system located in the northeast of building 3. The diversion structure high flow will be conveyed to curb outlet that discharge to the curb and gutter at 2nd street.

Drainage Area B4 consists of the east portion of Building 1, the west side of Building 2, the northwest side of Building 4, as well as landscape and pedestrian walkway areas. Runoff will be captured and conveyed by an area drain system that leads to a diversion structure. The diversion structure will have a low flow outlet leading to an MWS system located in the west median of the parking lot.

Drainage B5 consists of the south side of Building 2, the northeast side of Building 4, as well as landscape and pedestrian walkway areas. Runoff will be captured and conveyed via an area drain system that leads to a diversion structure at the west of Building 3. The diversion structure will have a low-flow outlet leading to an MWS system located in the west of Building 3.

Drainage B6.1 and B6.2 consist of the south side of Building 4, landscape, and parking lot areas. Runoff will be conveyed via a ribbon gutter and captured in a catch basin that leads to an MWS system located on the east side of the parking lot.

Drainage B7 consists of the west side of Building 3, landscape, pedestrian walkway, and pool areas. Runoff will be captured and conveyed via an area drain system that leads to a diversion structure at the west of Building 3. The diversion structure will have a low-flow outlet leading to an MWS system located in the west of Building 3.

The treated low flows from MWS units of drainage areas B4, B5, B6.1, B6.2 and B7 will be conveyed through a private low flow storm drain system. The 10-year flows from these areas will be conveyed through a separate private 10-year storm system.

This private low flow storm drain will connect to the existing 54'' RCP storm drain system in Buena Vista. The 10-year flows storm drain system will be discharged towards a parkway culvert at 2^{nd} Street.

Drainage C1 and C2 consist of the east side of Building 3, landscape, pedestrian walkway, and parking lot areas. Runoff will be captured and conveyed via an area drain system that leads to a diversion structure at the northeast corner of the property. The diversion structure will have a low-flow outlet that leads to an MWS system located in the northeast of the property. The 10-Year (high) flow from the diversion structure will be conveyed to a parkway culvert that discharges into the curb and gutter at Buena Vista.

The site will be graded as such to have overland runoff for severe storms and the finish floor is set at least a foot over the 100 year-storm.

Refer to Appendices 7.2 and 7.4 for Proposed Hydrology maps and calculations.

4.0 STREET CAPACITY ANALYSIS

The City of Corona Drainage Master Plan, along with City staff, has stated that the storm drain on Buena Vista Avenue is in deficient conditions. Street capacity analysis analyzed in Appendix 7.5.

The street capacity analysis, detailed in Appendix 7.5, indicates that for Buena Vista, the Q100 is 602.98 cfs, as per hydrology backup calculations. However, the existing 54-inch storm drain pipe can handle only 278.09 cfs. Consequently, the street capacity calculations are based on 325 cfs.

For 2nd Street, the capacity analysis is conducted with Buena Vista's Q100 because the City of Corona Drainage Master Plan did not assess the flow on 2nd Street at that time.

Street	Finish Floor (ft)	Water Surface (ft)	Normal Depth (inch)	Clearance (ft)
Buena Vista - 1	639.6	638.0	11.7	1.6
Buena Vista - 2	638.1	635.7	12.8	2.4
Buena Vista - 3	636.6	633.3	12.2	3.3
2 nd Street - 1	636.6	632.2	17.9	4.4

Refer to *Appendices 7.5* for Street capacity calculations.

5.0 DESIGN CRITERIA

- The proposed storm drain systems will be designed to be consistent with the following goals and guidelines:
- Onsite design storm is based on a 10-year frequency in sump conditions for catch basins and the connecting storm drains also use a 10-year frequency.
- Velocity should not exceed 20 FPS in a standard wall R.C.P.
- Where velocity exceeds 20 FPS, a special wall R.C.P. with a minimum of 1½-inch steel clearance on the inside surface shall be used.
- Maximum velocity in special cover R.C.P. shall be 45 FPS.
- On local streets one lane shall be free of storm water in a 10-year storm event.
- Maximum W.S. in CB's for design conditions shall be 0.5' below inlet (FL.) elevation.
- Once water is picked up in a storm drain, it should remain in the system.
- Pipe size may not be decreased downstream without the City's approval.

6.0 RESULTS AND CONCLUSIONS

A summary of the 10-year and 100-year peak flow analysis for existing and proposed conditions are provided in the table below. See Tables 5.1 to 5.5

As a result of the site development and improvements, the overall site proposed conditions flows will be comparable to slightly increasing from the existing conditions for the 10-year and 100-year events. The proposed overall site peak flows will slightly increase from the existing condition. The proposed overall site time of concentration (Tc) will slightly increase from the existing time of concentration.

The City of Corona Drainage Master Plan, along with City staff, has stated that the storm drain on Buena Vista Avenue is in deficient conditions. In Appendix 5, the street capacity analysis shows that during a 100-year storm event, the proposed building floors are at least 1 foot higher than the street's water. This data indicates that the system is doing well in preventing flooding and protecting the proposed buildings.

It is our opinion that the proposed storm drain system will not have an adverse effect on any of the existing or proposed improvements within the project or adjacent public streets. In addition, all design criteria outlined above will be met and provided in the final hydrology report. Hydrology Calculations for Tables below are provided in Appendices 2, 3, 4 and 5.

Overall Project Impacts Downstream

Table 5.1

14510 011							
Peak Q Summary							
Event	Existing (CFS)	Proposed (CFS)	Δ (CFS)	Percentage Change			
10-Year	8.3	8.5	0.2	1.0%			
100-Year	13.2	13.4	0.2	0.8%			

Overall Project Impacts to 2nd Street

Table 5.2

Peak Q Summary							
Event	Existing (CFS)	Proposed (CFS)	Δ (CFS)	Percentage Change			
10-Year	6.8	7.9	1.1	16.2%			
100-Year	10.8	12.3	1.5	13.9%			

Table 5.3

Time of Concentration Summary						
Event	Existing (minutes) ¹	Proposed (minutes)	Δ (minutes)	Percentage Change		
10-Year	7.8	8.0	0.2	-2.6%		
100-Year	7.9	8.0	0.1	-1.3%		

Overall Project Impacts to Buena Vista

Table 5.4

Peak Q Summary							
Event	Existing (CFS)	Proposed (CFS)	Δ (CFS)	Percentage Change			
10-Year	1.5	0.7	-0.8	-53.3%			
100-Year	2.3	1.1	-1.2	-52.2%			

Table 5.5

Time of Concentration Summary						
Event	Existing (minutes) ¹	Proposed (minutes)	Δ (minutes)	Percentage Change		
10-Year	6.2	5.2	-1.0	-19.3%		
100-Year	6.2	5.2	-1.0	-19.3%		

7.0 APPENDICES

APPENDIX 1 SUPPORTING MAPS AND PLANS

Soil Map, FEMA (FIRM) Map & Existing Improvement Plans

APPENDIX 2 HYDROLOGY MAPS

Existing and Proposed Conditions

APPENDIX 3 EXISTING HYDROLOGY CALCULATIONS

10 year & 100 year storm frequencies

APPENDIX 4 PROPOSED HYDROLOGY CALCULATIONS

10 year & 100 year storm frequencies

APPENDIX 5 PONDING EXHIBIT & STREET CAPACITY CROSS SECTIONS

APPENDIX 1

SUPPORTING MAPS AND PLANS

National Flood Hazard Layer FIRMette

250


500

1,000

1,500


2,000






Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT





Digital Data Available

No Digital Data Available

Unmapped




The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards


The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 8/10/2023 at 1:19 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.





RCFC&WCD Hydrology Manual



HYDROLOGIC SOILS GROUP MAP FOR CORONA-NORTH



MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils

Soil Map Unit Polygons



Soil Map Unit Points

Special Point Features

(o) Blowout

Borrow Pit

Clay Spot

Closed Depression

Gravel Pit

Gravelly Spot

Landfill

Lava Flow

Marsh or swamp

Mine or Quarry

Miscellaneous Water

Perennial Water

Rock Outcrop

♣ Saline Spot

Sandy Spot

Severely Eroded Spot

Sinkhole

Slide or Slip

Sodic Spot

Spoil Area

Stony Spot

Very Stony Spot

Wet Spot
 Other
 Othe

Special Line Features

Water Features

Δ

Streams and Canals

Transportation

Rails

Interstate Highways

US Routes

Major Roads

Local Roads

Background

Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15.800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Western Riverside Area, California Survey Area Data: Version 15, Sep 6, 2022

Soil map units are labeled (as space allows) for map scales 1:50.000 or larger.

Date(s) aerial images were photographed: Mar 14, 2022—Mar 17, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
GdC	Garretson gravelly very fine sandy loam, 2 to 8 percent slopes	4.2	100.0%
Totals for Area of Interest		4.2	100.0%

Western Riverside Area, California

GdC—Garretson gravelly very fine sandy loam, 2 to 8 percent slopes

Map Unit Setting

National map unit symbol: hcv5 Elevation: 50 to 3,000 feet

Mean annual precipitation: 12 to 25 inches Mean annual air temperature: 61 to 64 degrees F

Frost-free period: 250 to 350 days

Farmland classification: Prime farmland if irrigated

Map Unit Composition

Garretson and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of

the mapunit.

Description of Garretson

Setting

Landform: Alluvial fans

Landform position (three-dimensional): Tread

Down-slope shape: Linear Across-slope shape: Linear

Parent material: Alluvium derived from metasedimentary rock

Typical profile

H1 - 0 to 10 inches: gravelly very fine sandy loam

H2 - 10 to 53 inches: gravelly loam

H3 - 53 to 72 inches: loam

Properties and qualities

Slope: 2 to 8 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water supply, 0 to 60 inches: Moderate (about 7.4

inches)

Interpretive groups

Land capability classification (irrigated): 2e Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: B

Ecological site: R019XD029CA - LOAMY

Hydric soil rating: No

Minor Components

Perkins

Percent of map unit: 5 percent Hydric soil rating: No

Arbuckle

Percent of map unit: 5 percent Hydric soil rating: No


Cortina

Percent of map unit: 5 percent Hydric soil rating: No

Data Source Information

Soil Survey Area: Western Riverside Area, California

Survey Area Data: Version 15, Sep 6, 2022



INDEX OF SHEETS

SHEET NO.

DESCRIPTION

- TITLE SHEET
 - PLAN AND PROFILE
 - FROM **500** south of 91
 - FRWY, TO 635' NORTH OF
 - FROM **635** NORTH OF 91
 - FRWY, TO RAILROAD STREET

DRAINAGE DETAILS

GENERAL NOTES

- 1. ALL WORK AND MATERIALS SHALL COMPLY WITH THE SPECIFICATIONS NO. 4-378 AND STANDARD PLANS OF THE CITY OF CORONA, DEPARTMENT OF COMMUNITY DEVELOPMENT AND PUBLIC WORKS. THESE DRAWINGS AND THE DATA HEREIN ARE MADE A PART OF THE SPECIFICATIONS.
- 2. THE EXISTANCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OF STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS THESE LOCATIONS ARE APPROXIMATE AND SHALL BE CONFIRMED BY THE CONTRACTOR. SO THAT ANY NECESSARY ADJUSTMENT CAN BE MADE IN ALIGNMENT AND/OR GRADE OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR IS REQUIRED TO TAKE DUE PRE-CAUTIONARY MEASURES TO PROTECT ANY UTILITY LINES SHOWN AND ANY OTHER LINES NOT OF RECORD OR NOT SHOWN ON THESE PLANS.
- 3. ALL UTILITY COMPANIES TO BE GIVEN 48 HOURS NOTICE PRIOR TO WORKING AROUND THEIR FACILITIES. NOTICE BY CONTRACTOR
- 4. INSPECTION TO BE CALLED FOR THROUGH THE CITY OF CORONA (736-2259) 24 HOURS PRIOR TO STARTING WORK.
- 5. BEFORE WORK CAN BE STARTED THE CONTRACTOR MUST OBTAIN A PERMIT TO EXCAVATE IN THE CITY STREETS FROM THE CITY OF CORONA.
- 6. AS-BUILT DRAWINGS TO BE FURNISHED TO THE CITY OF CORONA AFTER COMPLETION OF CONSTRUCTION FURNISHED BY CONTRACTOR
- ALL MATERIALS AND METHODS TO BE SUBJECT TO APPROVAL OF THE CITY ENGINEER.
- 8. ALL BACKFILL TO BE CERTIFIED BY A SOILS ENGINEER
- 9. ALL FIRE HYDRANTS WHICH HAVE NOT BEEN ACCEPTED FOR SERVICE SHALL BE COVERED WITH A SACK INDICATING THAT THE HYDRANTS ARE NOT IN SERVICE.
- 10. WATER METER BOXES SHALL BE CONSIDERED TO BE PART OF THE PROJECT AND SHALL BE BROUGHT TO GRADE AND LEVELED BY THE CONTRACTOR.
- 11. ALL NEW OR EXISTING VALVE BOXES AND MANHOLES SHALL BE ADJUSTED TO GRADE AFTER PAVING IS COMPLETED. ADJUSTMENT BY CONTRACTOR
- 12. TRENCHES SHALL HAVE SHAPED BEDDING.
- 13. BACKFILL MATERIAL TO HAVE AN S.E. OF 30 (MIN).
- 14. BACKFILL TO BE IN 8" LIFTS IF TRENCH BOTTOM AND SIDES HAVE AN S.E. OF LESS
- 15. STOMPING OF BACKFILL PERMITTED IN 3' LIFTS.
- 16. CONTRACTOR TO REMOVE AND OR INSTALL PAVEMENT MARKINGS AND STRIPING AS REQUIRED BY THE ENGINEER.
- 17. CONTRACTOR SHALL NOT OPERATE ANY MAIN LINE WATER VALVE.
- 18. IF ANY EXISTING UTILITIES OR ANY OTHER FACILITIES CONFLICT WITH THE PROPOSED IMPROVEMENTS THE CONTRACTOR SHALL NOTIFY THE ENGINEER FOR RELOCATION BY OTHERS OR ALTERNATE DESIGN.
- 19. ALL UTILITIES SHALL BE INSTALLED, TESTED AND APPROVED PRIOR TO STREET
- 20. RELOCATION OF EXISTING PARKWAY SIGNS, METERS AND FIRE HYDRANTS AS REQUIRED BY THIS PROJECT SHALL BE RELOCATED BY THE CONTRACTOR IN ACCORDANCE WITH THE PROPOSAL FORM.
- 21. REMOVAL OF EXISTING PARKWAY TREES AS REQUIRED BY THIS PROJECT SHALL BE REMOVED BY THE CONTRACTOR IN ACCORDANCE WITH THE PROPOSAL FORM
- 22. EXISTING UTILITY POLE AND GAS METER RELOCATION WILL BE PERFORMED BY THE UTILITY COMPANY AT NO COST TO THE CONTRACTOR. HOWEVER, THE CONTRACTORS WORK SHALL BE COORDINATED WITH SAID RELOCATION AND/OR ADJUSTMENT.


TOPOGRAPHY LEGEND

CURB & GUTTER ASPH. CONC. PAVEMENT CONCRETE PAVEMENT POWER POLE TRAFFIC SIGNAL STREET LIGHT SIGN POST DEADMAN OUR DOWN GUY SIGNAL: OR PULL BOX GAS METER WATER METER FIRE HYDRANT. SPRINKLER MANHOLE PALM TREE HEDGES BUSHES FENCE CONC. BLOCK WALL PUBLIC. TELEPHONE

CITY OF CORONA

SPECIFICATION No. 4-378

BUENA VISTA AVENUE FROM 500' % 91 FRWY. TO RAILROAD STREET




APPLICABLE STANDARD PLANS CITY OF CORONA

- CURB AND GUTTER
- SIDEWALK DETAILS DRIVEWAY APPROACH
- DRIVEWAY APPROACH SOLID SIDEWALK WHEEL CHAIR RAMP
- WHEEL CHAIR RAMP
- CATCH BASIN TYPE "B"
- 203 CATCH BASIN DETAILS
- CONC. COLLAR
- 301 SEWER MANHOLE
- 408 WATER SERVICE CONNECTION
- 412 FIRE HYDRANT- INSTALLATION

LOS ANGELES CO. FLOOD CONTROL

2-D112 JUNCTION STRUCTURE NO. 2 2-D393 CONCRETE COLLAR CONSTRUCTION LEGEND

- CONSTRUCT .21 A.C. ON AGG. BASE FOG SEAL OVERALL.
- CONSTRUCT A.C. OVERLAY, FOG SEAL OVERALL.
- CONSTRUCT TYPE 8 CURB & GUTTER PER STD. 103.
- CONSTRUCT SIDEWALK PER STD. 104.
- CONSTRUCT DRIVEWAY APPROACH PER STD. 107.
- CONSTRUCT DRIVEWAY APPROACH PER STD. 108.
- CONSTRUCT WHEEL CHAIR RAMP PER STD. 116. CONSTRUCT WHEEL CHAIR RAMP PER STD. 117.
- CATCH BASIN TYPE B.
- PAINT TRAFFIC STRIPING CENTERLINE, STOP BARS & WORDING.



Grade To Exist Walk

Construction

or 14"/ft for new Walk

where indicated 5

WEACCO, INC. CIVIL ENGINEERS & LAND SURVEYORS 2768 KELLOGG WE CORONA 1720 PRINCIPAL ENGINEER

Grade as Indicated

LINE

14"/ft

Grade as shown in Profile

0.21' Asph Conc. Pav4

BUENA VISTA AVE.

STA 5+50 TO RAILROAD STREET

0.21 Asph; Conc*

RAILROAD STREET

0.45 Agg Base

0.60 Agg Base

10

Remove Exist.

LEVEL

Exist

SUBMITTED.

Grade to Exist Walk

construction

or 1/4"/ft for new walk


* TYPE 1C-AR 4000

AC. IN SINGLE LIFT

APPROVED. R.C.E. 18729 CITY ENGINEER


BUENA VISTA AVENUE SHEET I OF 4 SPECIFICATION No. 4-378 DRAW No. 1802


LOCATION MAP CITY OF CORONA





NOT CONSTRUCTED


77-57















DETAIL OF TYPICAL DRIVEWAY APPROACH PER STD. PLAN*108 MODIFIED AS SHOWN

NOT CONSTRUCTED


WEACCO, INC.	Designed by Drawn by Checked by			BENCH MARK	Engineering J. Cook	SabmittedApproved	CITY OF CORONA Dept. of Community Development & Public Works	Drawing No.
	GK PD JA			· SEE SHEET 2	mars Daw	by	BUENA VISTA AVENUE	1002
CIVIL ENGINEERS & LAND SURVEYORS		Reference Plans for		Scale .	Fire 218	RCE 25267 RCE 18729 Principal Engineer City Engineer	DETAILS & PROFILES	sh4 of4
2768 KELLOGG AVE., CORONA, 91720	Date 12:18-78 R.C.E. No. 9915		e By REVISIONS	App'd As Shown		, ritherpat Eugeneer ofty Eugeneer		77-57

APPENDIX 2

HYDROLOGY MAPS



LEGEND



HYDROLOGY NODE

TRIBUTARY AREAS

DMA A (TRIBUTARY TO 2ND ST):

TOTAL AREA: 0.72 AC

Q₁₀=1.57 CFS

Q₁₀₀=2.47 CFS

DMA B (TRIBUTARY TO 2ND ST)

TOTAL AREA: 2.75 AC

Q₁₀=5.27 CFS

Q₁₀₀=8.35 CFS

DMA C (TRIBUTARY TO BUENA VISTA):

TOTAL AREA: 0.71 AC

Q₁₀=1.49 CFS

Q₁₀₀=2.34 CFS

OVERALL SUMMARY:

TOTAL AREA: 4.18 AC
Q₁₀=8.33 CFS
Q₁₀₀=13.16 CFS

SITE PARAMETERS

HYDROLOGY SOIL GROUP: B

TOTAL DRAINAGE STUDY ACREAGE: 4.18 ACRES

(25% PERVIOUS USED FOR MOBILE HOME PARK)


FEMA FLOOD ZONE X PER FIRM MAP NO 06065C0689G


ZONE X = AREA OF MINIMAL FLOOD HAZARD



(100)

EXISTING HYDROLOGY - OVERVIEW
WEST 2ND APARTMENT
CORONA, CALIFORNIA





LEGEND

DRAINAGE STUDY LIMITS

DMA BOUNDARY

SUBAREA BOUNDARY

EXISTING STORM DRAIN

PROPOSED STORM DRAIN

AREA DESIGNATION

AREA (IN ACRES)

FLOW DIRECTION
FLOW LENGTH
FLOW RATE (CFS)

HYDROLOGY NODE

TRIBUTARY AREAS

DMA A (TOWARDS 2ND ST):

TOTAL AREA: 0.69 AC

Q₁₀=1.40 CFS

Q₁₀₀=2.20 CFS

 $\begin{array}{cccc} \underline{\mathsf{DMA}} & \mathsf{B} & (\mathsf{TOWARDS} & 2\mathsf{ND} & \mathsf{ST}) \\ & \mathsf{TOTAL} & \mathsf{AREA:} & 3.11 & \mathsf{AC} \\ \mathsf{Q}_{10} {=} 6.45 & \mathsf{CFS} \\ \mathsf{Q}_{100} {=} 10.14 & \mathsf{CFS} \end{array}$

DMA C (TOWARDS BUENA VISTA):

TOTAL AREA: 0.28 AC

Q₁₀=0.70 CFS

Q₁₀₀=1.09 CFS

RIGHT OF WAY DEDICAITON:
TOTAL AREA: 0.10 AC

 $\begin{array}{c} \underline{\text{OVERALL SUMMARY:}} \\ \hline \text{TOTAL AREA: 4.16 AC} \\ Q_{10} = 8.55 \text{ CFS} \\ Q_{100} = 13.43 \text{ CFS} \end{array}$

SITE PARAMETERS


HYDROLOGY SOIL GROUP: B

TOTAL DRAINAGE STUDY ACREAGE: 4.18 ACRES
(20% PERVIOUSNESS USED FOR APARTMENTS)

FAMILY APARTMENT: 3.39 ACRES
PERMANENT SUPPORTIVE HOUSING: 0.69 ACRES
RIGHT OF WAY DEDICATION: 0.10 ACRES

FEMA FLOOD ZONE X PER FIRM MAP NO 06065C0689G
ZONE X = AREA OF MINIMAL FLOOD HAZARD

PROPOSED HYDROLOGY - OVERVIEW WEST 2ND APARTMENT CORONA, CALIFORNIA





APPENDIX 3

EXISTING HYDROLOGY CALCULATIONS

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT (RCFC&WCD) 1978 HYDROLOGY MANUAL

(c) Copyright 1982-2016 Advanced Engineering Software (aes) (Rational Tabling Version 23.0)

Release Date: 07/01/2016 License ID 1355

Analysis prepared by:

```
*********************** DESCRIPTION OF STUDY ********************
                       CORONA APARTMENTS
                        EXISTING HYDROLOGY
                        10 YEAR STORM
 ******************
 FILE NAME: CRNAEX.DAT
 TIME/DATE OF STUDY: 09:36 02/15/2024
______
 USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:
 USER SPECIFIED STORM EVENT (YEAR) = 10.00
 SPECIFIED MINIMUM PIPE SIZE(INCH) = 3.00
 SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.90
 2-YEAR, 1-HOUR PRECIPITATION(INCH) = 0.520
 100-YEAR, 1-HOUR PRECIPITATION(INCH) = 1.320
 COMPUTED RAINFALL INTENSITY DATA:
 STORM EVENT = 10.00 1-HOUR INTENSITY(INCH/HOUR) = 0.858
 SLOPE OF INTENSITY DURATION CURVE = 0.4750
 RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
 NOTE: COMPUTE CONFLUENCE VALUES ACCORDING TO RCFC&WCD HYDROLOGY MANUAL
      AND IGNORE OTHER CONFLUENCE COMBINATIONS FOR DOWNSTREAM ANALYSES
 *USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL*
    HALF- CROWN TO STREET-CROSSFALL: CURB GUTTER-GEOMETRIES: MANNING
    WIDTH CROSSFALL IN- / OUT-/PARK- HEIGHT WIDTH LIP HIKE FACTOR
NO. (FT) (FT) SIDE / SIDE / WAY (FT) (FT) (FT) (n)
NO.
    30.0
         20.0 0.018/0.018/0.020
                                  0.67 2.00 0.0312 0.167 0.0150
 GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
   1. Relative Flow-Depth = 0.00 FEET
     as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
   2. (Depth) * (Velocity) Constraint = 6.0 (FT*FT/S)
 *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
  OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*
*********************
 FLOW PROCESS FROM NODE 10.00 TO NODE 20.00 IS CODE = 21
______
 >>>>RATTONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 275.00
 UPSTREAM ELEVATION(FEET) = 650.50
 DOWNSTREAM ELEVATION (FEET) = 643.80
 ELEVATION DIFFERENCE (FEET) =
                            6.70
 TC = 0.336*[(275.00**3)/(6.70)]**.2 = 6.677
   10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.434
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8323
 SOIL CLASSIFICATION IS "B"
```

```
SUBAREA RUNOFF(CFS) =
                   0.37 TOTAL RUNOFF(CFS) =
 TOTAL AREA (ACRES) =
******************
                                       40.00 \text{ IS CODE} = 21
 FLOW PROCESS FROM NODE 30.00 TO NODE
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) =
 UPSTREAM ELEVATION(FEET) = 647.30
 DOWNSTREAM ELEVATION (FEET) =
                           645.40
 ELEVATION DIFFERENCE (FEET) =
                             1.90
 TC = 0.336*[(74.00**3)/(1.90)]**.2 =
 COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
   10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.792
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8386
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 0.82
                     0.35 TOTAL RUNOFF(CFS) =
 TOTAL AREA(ACRES) =
FLOW PROCESS FROM NODE 40.00 TO NODE 50.00 IS CODE = 91
 _____
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA
______
 UPSTREAM NODE ELEVATION (FEET) = 645.40
 DOWNSTREAM NODE ELEVATION (FEET) = 640.00
CHANNEL LENGTH THRU SUBAREA (FEET) = 226.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.00300
 MAXIMUM DEPTH (FEET) = 5.00
  10 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.357
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8308
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.76
 AVERAGE FLOW DEPTH(FEET) = 0.10 FLOOD WIDTH(FEET) =
 SUBAREA AREA(ACRES) = 0.75 SUBAREA RUNOFF(CFS) = 1.47 TOTAL AREA(ACRES) = 1.1
                                                            2 29
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.11 FLOOD WIDTH (FEET) = 37.56
 FLOW VELOCITY (FEET/SEC.) = 1.88 DEPTH*VELOCITY (FT*FT/SEC) = 0.21
 LONGEST FLOWPATH FROM NODE 30.00 TO NODE 50.00 = 300.00 FEET.
 FLOW PROCESS FROM NODE 50.00 TO NODE 60.00 IS CODE = 91
                       _____
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION(FEET) = 640.00
 DOWNSTREAM NODE ELEVATION (FEET) = 636.20
CHANNEL LENGTH THRU SUBAREA (FEET) = 86.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.00200
 MAXIMUM DEPTH (FEET) = 5.00
   10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.263
```

0.75

```
MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8288
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) = 2.55
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 2.24
 AVERAGE FLOW DEPTH(FEET) = 0.10 FLOOD WIDTH(FEET) = 44.20
 "V" GUTTER FLOW TRAVEL TIME(MIN.) = 0.64 Tc(MIN.) = 7.78
 SUBAREA AREA (ACRES) = 0.28 SUBAREA RUNOFF (CFS) = 0.53
 TOTAL AREA(ACRES) =
                       1.4
                                 PEAK FLOW RATE(CFS) =
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.10 FLOOD WIDTH (FEET) = 46.61
 FLOW VELOCITY (FEET/SEC.) = 2.25 DEPTH*VELOCITY (FT*FT/SEC) = 0.23
 LONGEST FLOWPATH FROM NODE 30.00 TO NODE 60.00 = 386.00 FEET.
*************
                       70.00 TO NODE
 FLOW PROCESS FROM NODE
                                       80.00 \text{ IS CODE} = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH(FEET) = 300.00
 UPSTREAM ELEVATION(FEET) = 644.80
 DOWNSTREAM ELEVATION (FEET) =
 ELEVATION DIFFERENCE(FEET) =
                            7.00
 TC = 0.336*[(300.00**3)/(7.00)]**.2 = 6.974
  10 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.384
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8313
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 1.55
 TOTAL AREA(ACRES) =
                     0.78 TOTAL RUNOFF(CFS) =
******************
 FLOW PROCESS FROM NODE 80.00 TO NODE 90.00 IS CODE = 91
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 637.80
 DOWNSTREAM NODE ELEVATION(FEET) = 633.10
CHANNEL LENGTH THRU SUBAREA(FEET) = 128.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.00200
 MAXIMUM DEPTH (FEET) = 5.00
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.230
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8281
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 2.02
 AVERAGE FLOW DEPTH(FEET) = 0.10 FLOOD WIDTH(FEET) =
 "V" GUTTER FLOW TRAVEL TIME (MIN.) = 1.05 TC (MIN.) = 8.03

SUBAREA AREA (ACRES) = 0.94 SUBAREA RUNOFF (CFS) = 1.74

TOTAL AREA (ACRES) = 1.7 PEAK FLOW RATE (CFS) =
 TOTAL AREA(ACRES) =
                      1.7
                               PEAK FLOW RATE(CFS) =
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.11 FLOOD WIDTH (FEET) = 52.64
 FLOW VELOCITY (FEET/SEC.) = 2.12 DEPTH*VELOCITY (FT*FT/SEC) = 0.23
 LONGEST FLOWPATH FROM NODE
                          70.00 TO NODE
                                          90.00 = 428.00 FEET.
FLOW PROCESS FROM NODE 100.00 TO NODE 110.00 IS CODE = 21
```

```
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
      ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) =
 UPSTREAM ELEVATION (FEET) = 642.20
 DOWNSTREAM ELEVATION(FEET) = 635.00

ELEVATION DIFFERENCE(FEET) = 7.20

TC = 0.336*[( 250.00**3)/( 7.20)]**.2 = 6.216
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.518
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8339
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 1.49
TOTAL AREA(ACRES) = 0.71 TOTAL RUNOFF(CFS) =
                     1.49
______
 END OF STUDY SUMMARY:
 TOTAL AREA (ACRES)
                         0.7 TC(MIN.) =
 PEAK FLOW RATE (CFS) = 1.49
______
______
```

END OF RATIONAL METHOD ANALYSIS

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT (RCFC&WCD) 1978 HYDROLOGY MANUAL

(c) Copyright 1982-2016 Advanced Engineering Software (aes) (Rational Tabling Version 23.0)

Release Date: 07/01/2016 License ID 1355

Analysis prepared by:

Fuscoe Engineering 16795 Von Karman Ave Stel00 Irvine CA 92606

```
CORONA APARTMENTS
                      EXISTING HYDROLOGY
                       100 YEAR STORM
******************
 FILE NAME: CRNAEX.DAT
 TIME/DATE OF STUDY: 11:18 11/09/2023
 USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:
 ______
 USER SPECIFIED STORM EVENT (YEAR) = 100.00
 SPECIFIED MINIMUM PIPE SIZE (INCH) = 3.00
 SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.90
 2-YEAR, 1-HOUR PRECIPITATION(INCH) = 0.520
 100-YEAR, 1-HOUR PRECIPITATION(INCH) = 1.320
 COMPUTED RAINFALL INTENSITY DATA:
 STORM EVENT = 100.00 1-HOUR INTENSITY(INCH/HOUR) =
 SLOPE OF INTENSITY DURATION CURVE = 0.4750
 RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
 NOTE: COMPUTE CONFLUENCE VALUES ACCORDING TO RCFC&WCD HYDROLOGY MANUAL
      AND IGNORE OTHER CONFLUENCE COMBINATIONS FOR DOWNSTREAM ANALYSES
 *USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL*
   HALF- CROWN TO STREET-CROSSFALL: CURB GUTTER-GEOMETRIES: MANNING
   WIDTH CROSSFALL IN- / OUT-/PARK- HEIGHT WIDTH LIP HIKE FACTOR
         (FT) SIDE / SIDE/ WAY (FT)
                                       (FT) (FT) (FT)
NO.
   (FT)
20.0 0.018/0.018/0.020 0.67 2.00 0.0312 0.167 0.0150
 1 30.0
 GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
   1. Relative Flow-Depth = 0.00 FEET
    as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
   2. (Depth) * (Velocity) Constraint = 6.0 (FT*FT/S)
 *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
  OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*
*******************
 FLOW PROCESS FROM NODE 10.00 TO NODE 20.00 IS CODE = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
      ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 275.00
 UPSTREAM ELEVATION (FEET) = 650.50
 DOWNSTREAM ELEVATION (FEET) = 643.80
```

```
ELEVATION DIFFERENCE (FEET) =
                          6.70
 TC = 0.336*[(275.00**3)/(6.70)]**.2 = 6.677
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.746
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8508
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 1.18
 TOTAL AREA (ACRES) =
                    0.37 TOTAL RUNOFF(CFS) =
******************
 FLOW PROCESS FROM NODE 30.00 TO NODE
                                    40.00 \text{ IS CODE} = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS
______
      ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 74.00
 UPSTREAM ELEVATION (FEET) = 647.30
 DOWNSTREAM ELEVATION (FEET) =
 ELEVATION DIFFERENCE (FEET) = 1.90
TC = 0.336*[( 74.00**3)/( 1.90)]**.2 = 3.908
 COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.297
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8559
 SOIL CLASSIFICATION IS "B"
*************
 FLOW PROCESS FROM NODE 40.00 TO NODE 50.00 IS CODE = 91
______
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 645.40
 DOWNSTREAM NODE ELEVATION(FEET) = 640.00
 CHANNEL LENGTH THRU SUBAREA (FEET) = 226.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.00300
 MAXIMUM DEPTH(FEET) = 5.00
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.661
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8499
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.88
 AVERAGE FLOW DEPTH(FEET) = 0.11 FLOOD WIDTH(FEET) = 39.17
 "V" GUTTER FLOW TRAVEL TIME(MIN.) = 2.00 Tc(MIN.) = 7.00 SUBAREA AREA(ACRES) = 0.75 SUBAREA RUNOFF(CFS) = 2.33
                               PEAK FLOW RATE(CFS) =
 TOTAL AREA (ACRES) =
                                                      3.62
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH(FEET) = 0.12 FLOOD WIDTH(FEET) = 47.21
 FLOW VELOCITY(FEET/SEC.) = 1.98 DEPTH*VELOCITY(FT*FT/SEC) = 0.24
LONGEST FLOWPATH FROM NODE 30.00 TO NODE 50.00 = 300.00 FE
                        30.00 TO NODE 50.00 = 300.00 FEET.
FLOW PROCESS FROM NODE 50.00 TO NODE 60.00 IS CODE = 91
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 640.00
 DOWNSTREAM NODE ELEVATION (FEET) = 636.20
 CHANNEL LENGTH THRU SUBAREA (FEET) = 86.00
```

```
PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.00200
 MAXIMUM DEPTH (FEET) = 5.00
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.517
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8484
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 2.31
 AVERAGE FLOW DEPTH(FEET) = 0.11 FLOOD WIDTH(FEET) =
 "V" GUTTER FLOW TRAVEL TIME (MIN.) = 0.62 Tc (MIN.) =
                                                    7.62
 SUBAREA AREA(ACRES) = 0.28 SUBAREA RUNOFF(CFS) = 0.84
TOTAL AREA(ACRES) = 1.4 PEAK FLOW RATE(CFS) =
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH(FEET) = 0.11 FLOOD WIDTH(FEET) = 58.67
 FLOW VELOCITY(FEET/SEC.) = 2.37 DEPTH*VELOCITY(FT*FT/SEC) = 0.27
 LONGEST FLOWPATH FROM NODE 30.00 TO NODE
                                          60.00 = 386.00 \text{ FEET.}
********************
 FLOW PROCESS FROM NODE 70.00 TO NODE 80.00 IS CODE = 21
_____
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 300.00
 UPSTREAM ELEVATION (FEET) = 644.80
 DOWNSTREAM ELEVATION (FEET) = 637.80
 ELEVATION DIFFERENCE (FEET) =
                             7.00
 TC = 0.336*[(300.00**3)/(7.00)]**.2 = 6.974
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.669
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8500
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 2.43
 TOTAL AREA(ACRES) =
                     0.78 TOTAL RUNOFF(CFS) =
******************
 FLOW PROCESS FROM NODE 80.00 TO NODE 90.00 IS CODE = 91
______
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA
______
 UPSTREAM NODE ELEVATION (FEET) = 637.80
 DOWNSTREAM NODE ELEVATION(FEET) = 633.10
 CHANNEL LENGTH THRU SUBAREA (FEET) = 128.00
 "V" GUTTER WIDTH(FEET) = 5.00 GUTTER HIKE(FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.00200
 MAXIMUM DEPTH(FEET) = 5.00
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.447
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8476
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 2.18
 AVERAGE FLOW DEPTH(FEET) = 0.11 FLOOD WIDTH(FEET) =
 "V" GUTTER FLOW TRAVEL TIME (MIN.) = 0.98 Tc (MIN.) = 7.95

SUBAREA AREA (ACRES) = 0.94 SUBAREA RUNOFF (CFS) = 2.75

TOTAL AREA (ACRES) = 1.7
 TOTAL AREA (ACRES) =
                       1.7
                                  PEAK FLOW RATE(CFS) =
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH(FEET) = 0.12 FLOOD WIDTH(FEET) = 64.70
 FLOW VELOCITY (FEET/SEC.) = 2.30 DEPTH*VELOCITY (FT*FT/SEC) = 0.27
```

"V" GUTTER WIDTH(FEET) = 5.00 GUTTER HIKE(FEET) = 0.050

```
********************
 FLOW PROCESS FROM NODE 100.00 TO NODE 110.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS
______
     ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS MOBILE HOME PARK
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 250.00
 UPSTREAM ELEVATION (FEET) = 642.20
 DOWNSTREAM ELEVATION (FEET) = 635.00
 ELEVATION DIFFERENCE (FEET) = 7.20
TC = 0.336*[( 250.00**3)/( 7.20)]**.2 = 6.216
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.875
 MOBILE HOME PARK DEVELOPMENT RUNOFF COEFFICIENT = .8521
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 2.34

TOTAL AREA(ACRES) = 0.71 TOTAL RUNOFF(CFS) = 2.34
_____
 END OF STUDY SUMMARY:
 TOTAL AREA(ACRES) = 0.7
PEAK FLOW RATE(CFS) = 2.34
                     0.7 \text{ TC (MIN.)} = 6.22
______
______
 END OF RATIONAL METHOD ANALYSIS
```

LONGEST FLOWPATH FROM NODE 70.00 TO NODE 90.00 = 428.00 FEET.

APPENDIX 4

PROPOSED HYDROLOGY CALCULATIONS

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT (RCFC&WCD) 1978 HYDROLOGY MANUAL

(c) Copyright 1982-2016 Advanced Engineering Software (aes) (Rational Tabling Version 23.0)

Release Date: 07/01/2016 License ID 1355

Analysis prepared by:

```
*********************** DESCRIPTION OF STUDY ********************
                     CORONA 2ND STREET
                     PROPOSED CONDITIONS
                     10 YEAR STORM
 ******************
 FILE NAME: CORONAPS.DAT
 TIME/DATE OF STUDY: 13:05 02/15/2024
______
 USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:
 USER SPECIFIED STORM EVENT (YEAR) = 10.00
 SPECIFIED MINIMUM PIPE SIZE(INCH) = 3.00
 SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.01
 2-YEAR, 1-HOUR PRECIPITATION(INCH) = 0.520
 100-YEAR, 1-HOUR PRECIPITATION(INCH) = 1.320
 COMPUTED RAINFALL INTENSITY DATA:
 STORM EVENT = 10.00 1-HOUR INTENSITY(INCH/HOUR) = 0.858
 SLOPE OF INTENSITY DURATION CURVE = 0.4750
 RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
 NOTE: COMPUTE CONFLUENCE VALUES ACCORDING TO RCFC&WCD HYDROLOGY MANUAL
      AND IGNORE OTHER CONFLUENCE COMBINATIONS FOR DOWNSTREAM ANALYSES
 *USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL*
    HALF- CROWN TO STREET-CROSSFALL: CURB GUTTER-GEOMETRIES: MANNING
    WIDTH CROSSFALL IN- / OUT-/PARK- HEIGHT WIDTH LIP HIKE FACTOR
NO. (FT) (FT) SIDE / SIDE / WAY (FT) (FT) (FT) (n)
NO.
    30.0
         20.0 0.018/0.018/0.020
                                  0.67 2.00 0.0312 0.167 0.0150
 GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
   1. Relative Flow-Depth = 0.00 FEET
     as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
   2. (Depth) * (Velocity) Constraint = 6.0 (FT*FT/S)
 *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
  OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*
*********************
 FLOW PROCESS FROM NODE 10.00 TO NODE 15.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 356.00
 UPSTREAM ELEVATION(FEET) = 649.00
 DOWNSTREAM ELEVATION (FEET) = 642.10
 ELEVATION DIFFERENCE (FEET) =
                            6.90
 TC = 0.323*[(356.00**3)/(6.90)]**.2 = 7.446
   10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.311
 USER-SPECIFIED RUNOFF COEFFICIENT = .8439
 SOIL CLASSIFICATION IS "B"
```

```
SUBAREA RUNOFF(CFS) =
                     1.40
                  0.72 TOTAL RUNOFF(CFS) =
 TOTAL AREA (ACRES) =
******************
 FLOW PROCESS FROM NODE 20.00 TO NODE
                                    25.00 \text{ IS CODE} = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
_____
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 205.00
 UPSTREAM ELEVATION(FEET) = 645.50
 DOWNSTREAM ELEVATION (FEET) =
                         640.50
 ELEVATION DIFFERENCE (FEET) =
                           5.00
 TC = 0.323*[(205.00**3)/(5.00)]**.2 =
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.623
 USER-SPECIFIED RUNOFF COEFFICIENT = .8486
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 0.71
 TOTAL AREA(ACRES) = 0.32 TOTAL RUNOFF(CFS) = 0.71
****************
 FLOW PROCESS FROM NODE 30.00 TO NODE
                                   31.00 \text{ IS CODE} = 21
 ______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K^*[(LENGTH^{**}3)/(ELEVATION CHANGE)]^{**}.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 176.00
 UPSTREAM ELEVATION (FEET) = 641.50
 DOWNSTREAM ELEVATION (FEET) = 638.50
 ELEVATION DIFFERENCE (FEET) =
                           3.00
                         3.00)]**.2 = 5.763
 TC = 0.323*[(176.00**3)/(
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.610
 USER-SPECIFIED RUNOFF COEFFICIENT = .8484
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) =
                      0.18
                    0.08 TOTAL RUNOFF(CFS) =
 TOTAL AREA(ACRES) =
******************
 FLOW PROCESS FROM NODE 31.00 TO NODE 35.00 IS CODE = 91
______
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 638.50
 DOWNSTREAM NODE ELEVATION(FEET) = 635.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 239.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.02000
 MAXIMUM DEPTH (FEET) = 5.00
   10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.200
 USER-SPECIFIED RUNOFF COEFFICIENT = .8419
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.60
 AVERAGE FLOW DEPTH(FEET) = 0.08 FLOOD WIDTH(FEET) = 6.51
 "V" GUTTER FLOW TRAVEL TIME (MIN.) = 2.49 Tc (MIN.) = 8.25
 SUBAREA AREA(ACRES) = 0.26 SUBAREA RUNOFF(CFS) = 0.48 TOTAL AREA(ACRES) = 0.3 PEAK FLOW RATE(CFS) =
                                                      0.66
```

```
END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.09 FLOOD WIDTH (FEET) = 7.95
 FLOW VELOCITY (FEET/SEC.) = 1.80 DEPTH*VELOCITY (FT*FT/SEC) = 0.16
 LONGEST FLOWPATH FROM NODE 30.00 TO NODE 35.00 =
                                               415.00 FEET.
************************
 FLOW PROCESS FROM NODE 20.00 TO NODE 50.00 IS CODE = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
      ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 164.00
 UPSTREAM ELEVATION (FEET) = 645.50
 DOWNSTREAM ELEVATION (FEET) =
                        641.50
 ELEVATION DIFFERENCE (FEET) =
 TC = 0.323*[(164.00**3)/(4.00)]**.2 =
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.737
 USER-SPECIFIED RUNOFF COEFFICIENT = .8502
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) =
                    0.67
                   0.29 TOTAL RUNOFF(CFS) =
 TOTAL AREA(ACRES) =
*****
 FLOW PROCESS FROM NODE 40.00 TO NODE
                                  45.00 \text{ IS CODE} = 21
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
_____
      ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 216.00
 UPSTREAM ELEVATION (FEET) = 644.00
 DOWNSTREAM ELEVATION (1222)

ELEVATION DIFFERENCE (FEET) = 2.00

2.00)]**.2 = 2.00
                        642.00
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.369
 USER-SPECIFIED RUNOFF COEFFICIENT = .8448
 SOIL CLASSIFICATION IS "B"
********************
 FLOW PROCESS FROM NODE 50.00 TO NODE 75.00 IS CODE = 91
______
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 641.50
 DOWNSTREAM NODE ELEVATION(FEET) = 638.10
CHANNEL LENGTH THRU SUBAREA(FEET) = 267.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.02000
 MAXIMUM DEPTH (FEET) = 5.00
  10 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.090
 USER-SPECIFIED RUNOFF COEFFICIENT = .8399
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 2.09
 AVERAGE FLOW DEPTH(FEET) = 0.13 FLOOD WIDTH(FEET) = 12.18
 "V" GUTTER FLOW TRAVEL TIME (MIN.) = 2.13 Tc(MIN.) = 9.19
                            SUBAREA RUNOFF(CFS) = 1.83
 SUBAREA AREA(ACRES) = 1.04
```

```
TOTAL AREA(ACRES) = 1.4
                               PEAK FLOW RATE(CFS) =
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.16 FLOOD WIDTH (FEET) = 14.59
 FLOW VELOCITY (FEET/SEC.) = 2.30 DEPTH*VELOCITY (FT*FT/SEC) = 0.36
                         40.00 TO NODE 75.00 = 483.00 FEET.
 LONGEST FLOWPATH FROM NODE
********************
 FLOW PROCESS FROM NODE 60.00 TO NODE 65.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K^*[(LENGTH^{**}3)/(ELEVATION CHANGE)]^{**}.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 216.00
 UPSTREAM ELEVATION (FEET) = 643.50
 DOWNSTREAM ELEVATION (FEET) = 639.50
 ELEVATION DIFFERENCE (FEET) = 4.00
TC = 0.323*[( 216.00**3)/( 4.00)]**.2 = 6.153
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.530
 USER-SPECIFIED RUNOFF COEFFICIENT = .8473
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 0.77

TOTAL AREA(ACRES) = 0.36 TOTAL RUNOFF(CFS) =
*************
 FLOW PROCESS FROM NODE 80.00 TO NODE 90.00 IS CODE = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 87.00
 UPSTREAM ELEVATION (FEET) = 640.20
 ELEVATION (FEET) = 637.70

ELEVATION DIFFERENCE (FEET) = 2.50

TC = 0.323*[( 87 00***)
                          2.50)]**.2 =
 COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
   10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.792
 USER-SPECIFIED RUNOFF COEFFICIENT = .8509
 SOIL CLASSIFICATION IS "B"
                      0.24
 SUBAREA RUNOFF(CFS) =
                    0.10 TOTAL RUNOFF(CFS) =
 TOTAL AREA(ACRES) =
******************
 FLOW PROCESS FROM NODE 100.00 TO NODE 110.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
_____
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 167.00
 UPSTREAM ELEVATION(FEET) = 638.50
 DOWNSTREAM ELEVATION(FEET) =
                         634.50
 ELEVATION DIFFERENCE (FEET) =
                          4.00
 TC = 0.323*[(167.00**3)/(4.00)]**.2 = 5.273
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.722
 USER-SPECIFIED RUNOFF COEFFICIENT = .8500
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) =
```

```
TOTAL AREA(ACRES) = 0.20 TOTAL RUNOFF(CFS) =
******************
 FLOW PROCESS FROM NODE 120.00 TO NODE 130.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
      ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 117.00
 UPSTREAM ELEVATION(FEET) = 639.50
 DOWNSTREAM ELEVATION (FEET) =
                       638.00
 ELEVATION DIFFERENCE (FEET) = 1.50
TC = 0.323*[( 117.00**3)/( 1.50)]**.2 = 5.182
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.745
 USER-SPECIFIED RUNOFF COEFFICIENT = .8503
 SOIL CLASSIFICATION IS "B"
                   0.61
 SUBAREA RUNOFF (CFS) =
 TOTAL AREA(ACRES) =
                  0.26 TOTAL RUNOFF(CFS) =
*****
 FLOW PROCESS FROM NODE 140.00 TO NODE 150.00 IS CODE = 21
 _____
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS
_____
      ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 154.00
 UPSTREAM ELEVATION (FEET) = 637.00
 DOWNSTREAM ELEVATION (FEET) = 635.50
 ELEVATION DIFFERENCE (FEET) = 1.50
TC = 0.323*[( 154.00**3)/( 1.50)]**.2 = 6.111
  10 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.538
 USER-SPECIFIED RUNOFF COEFFICIENT = .8474
 SOIL CLASSIFICATION IS "B"
 SULD CLASSITION SUBAREA RUNOFF (CFS) = 0.39

TOTAL AREA (ACRES) = 0.18 TOTAL RUNOFF (CFS) = 0.39
______
 END OF STUDY SUMMARY:
                       0.2 TC(MIN.) =
 TOTAL AREA (ACRES) =
                                      6.11
 PEAK FLOW RATE(CFS) =
                      0.39
______
```

END OF RATIONAL METHOD ANALYSIS

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT (RCFC&WCD) 1978 HYDROLOGY MANUAL

(c) Copyright 1982-2016 Advanced Engineering Software (aes) (Rational Tabling Version 23.0)

Release Date: 07/01/2016 License ID 1355

Analysis prepared by:

```
*********************** DESCRIPTION OF STUDY ********************
                     CORONA 2ND STREET
                     PROPOSED CONDITIONS
                     100 YEAR STORM
 ******************
 FILE NAME: CORONAPS.DAT
 TIME/DATE OF STUDY: 13:06 02/15/2024
______
 USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:
 USER SPECIFIED STORM EVENT(YEAR) = 100.00
 SPECIFIED MINIMUM PIPE SIZE(INCH) = 3.00
 SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.01
 2-YEAR, 1-HOUR PRECIPITATION(INCH) = 0.520
 100-YEAR, 1-HOUR PRECIPITATION(INCH) = 1.320
 COMPUTED RAINFALL INTENSITY DATA:
 STORM EVENT = 100.00 1-HOUR INTENSITY(INCH/HOUR) = 1.320
 SLOPE OF INTENSITY DURATION CURVE = 0.4750
 RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
 NOTE: COMPUTE CONFLUENCE VALUES ACCORDING TO RCFC&WCD HYDROLOGY MANUAL
      AND IGNORE OTHER CONFLUENCE COMBINATIONS FOR DOWNSTREAM ANALYSES
 *USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL*
    HALF- CROWN TO STREET-CROSSFALL: CURB GUTTER-GEOMETRIES: MANNING
    WIDTH CROSSFALL IN- / OUT-/PARK- HEIGHT WIDTH LIP HIKE FACTOR
NO. (FT) (FT) SIDE / SIDE / WAY (FT) (FT) (FT) (n)
NO.
    30.0
         20.0 0.018/0.018/0.020
                                  0.67 2.00 0.0312 0.167 0.0150
 GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
   1. Relative Flow-Depth = 0.00 FEET
     as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
   2. (Depth) * (Velocity) Constraint = 6.0 (FT*FT/S)
 *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
  OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*
*********************
 FLOW PROCESS FROM NODE 10.00 TO NODE 15.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 356.00
 UPSTREAM ELEVATION(FEET) = 649.00
 DOWNSTREAM ELEVATION (FEET) = 642.10
 ELEVATION DIFFERENCE (FEET) =
                            6.90
 TC = 0.323*[(356.00**3)/(6.90)]**.2 = 7.446
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.557
 USER-SPECIFIED RUNOFF COEFFICIENT = .8590
 SOIL CLASSIFICATION IS "B"
```

```
SUBAREA RUNOFF(CFS) =
                     2.20
                  0.72 TOTAL RUNOFF(CFS) =
 TOTAL AREA (ACRES) =
******************
 FLOW PROCESS FROM NODE 20.00 TO NODE 25.00 IS CODE = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
_____
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 205.00
 UPSTREAM ELEVATION(FEET) = 645.50
 DOWNSTREAM ELEVATION (FEET) =
                         640.50
 ELEVATION DIFFERENCE (FEET) =
                           5.00
 TC = 0.323*[(205.00**3)/(5.00)]**.2 =
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.037
 USER-SPECIFIED RUNOFF COEFFICIENT = .8629
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 1.11
 TOTAL AREA(ACRES) =
                   0.32 TOTAL RUNOFF (CFS) = 1.11
****************
 FLOW PROCESS FROM NODE 30.00 TO NODE
                                  31.00 \text{ IS CODE} = 21
 ______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K^*[(LENGTH^{**}3)/(ELEVATION CHANGE)]^{**}.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 176.00
 UPSTREAM ELEVATION (FEET) = 641.50
 DOWNSTREAM ELEVATION (FEET) = 638.50
 ELEVATION DIFFERENCE (FEET) =
                           3.00
 TC = 0.323*[(176.00**3)/(3.00)]**.2 =
                                      5.763
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.017
 USER-SPECIFIED RUNOFF COEFFICIENT = .8628
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) =
                      0.28
                    0.08 TOTAL RUNOFF(CFS) =
 TOTAL AREA(ACRES) =
******************
 FLOW PROCESS FROM NODE 31.00 TO NODE 35.00 IS CODE = 91
______
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 638.50
 DOWNSTREAM NODE ELEVATION(FEET) = 635.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 239.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.02000
 MAXIMUM DEPTH (FEET) = 5.00
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.444
 USER-SPECIFIED RUNOFF COEFFICIENT = .8580
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.81
 AVERAGE FLOW DEPTH(FEET) = 0.09 FLOOD WIDTH(FEET) = 7.95
 "V" GUTTER FLOW TRAVEL TIME (MIN.) = 2.20 Tc (MIN.) = 7.97
 SUBAREA AREA(ACRES) = 0.26 SUBAREA RUNOFF(CFS) = 0.77
TOTAL AREA(ACRES) = 0.3 PEAK FLOW RATE(CFS) =
```

```
END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.11 FLOOD WIDTH (FEET) = 9.76
 FLOW VELOCITY (FEET/SEC.) = 1.99 DEPTH*VELOCITY (FT*FT/SEC) = 0.21
 LONGEST FLOWPATH FROM NODE 30.00 TO NODE 35.00 =
                                                415.00 FEET.
************************
 FLOW PROCESS FROM NODE 20.00 TO NODE 50.00 IS CODE = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 164.00
 UPSTREAM ELEVATION (FEET) = 645.50
 DOWNSTREAM ELEVATION (FEET) =
                        641.50
 ELEVATION DIFFERENCE (FEET) =
 TC = 0.323*[(164.00**3)/(4.00)]**.2 =
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.212
 USER-SPECIFIED RUNOFF COEFFICIENT = .8641
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 1.06

TOTAL AREA(ACRES) = 0.29 TOTAL RUNOFF(CFS) = 1.06
*****
 FLOW PROCESS FROM NODE 40.00 TO NODE
                                  45.00 \text{ IS CODE} = 21
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
_____
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 216.00
 UPSTREAM ELEVATION (FEET) = 644.00
 DOWNSTREAM ELEVATION (LLL),
ELEVATION DIFFERENCE (FEET) = 2.00
2.00)]**.2 =
                        642.00
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.646
 USER-SPECIFIED RUNOFF COEFFICIENT = .8598
 SOIL CLASSIFICATION IS "B"
********************
 FLOW PROCESS FROM NODE 50.00 TO NODE 75.00 IS CODE = 91
______
 >>>>COMPUTE "V" GUTTER FLOW TRAVEL TIME THRU SUBAREA<
______
 UPSTREAM NODE ELEVATION (FEET) = 641.50
 DOWNSTREAM NODE ELEVATION(FEET) = 638.10
CHANNEL LENGTH THRU SUBAREA(FEET) = 267.00
 "V" GUTTER WIDTH (FEET) = 5.00 GUTTER HIKE (FEET) = 0.050
 PAVEMENT LIP(FEET) = 0.010 MANNING'S N = .0150
 PAVEMENT CROSSFALL (DECIMAL NOTATION) = 0.02000
 MAXIMUM DEPTH (FEET) = 5.00
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.251
 USER-SPECIFIED RUNOFF COEFFICIENT = .8561
 SOIL CLASSIFICATION IS "B"
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 2.31
 AVERAGE FLOW DEPTH(FEET) = 0.16 FLOOD WIDTH(FEET) = 14.71
 "V" GUTTER FLOW TRAVEL TIME(MIN.) = 1.93 Tc(MIN.) = 9.00
                            SUBAREA RUNOFF(CFS) = 2.89
 SUBAREA AREA(ACRES) = 1.04
```

```
TOTAL AREA(ACRES) = 1.4
                               PEAK FLOW RATE(CFS) =
 END OF SUBAREA "V" GUTTER HYDRAULICS:
 DEPTH (FEET) = 0.19 FLOOD WIDTH (FEET) = 17.60
 FLOW VELOCITY (FEET/SEC.) = 2.53 DEPTH*VELOCITY (FT*FT/SEC) = 0.47
 LONGEST FLOWPATH FROM NODE
                         40.00 \text{ TO NODE} 75.00 = 483.00 \text{ FEET.}
********************
 FLOW PROCESS FROM NODE 60.00 TO NODE 65.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K^*[(LENGTH^{**}3)/(ELEVATION CHANGE)]^{**}.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 216.00
 UPSTREAM ELEVATION (FEET) = 643.50
 DOWNSTREAM ELEVATION (FEET) = 639.50
 ELEVATION DIFFERENCE (FEET) = 4.00
TC = 0.323*[( 216.00**3)/( 4.00)]**.2 = 6.153
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.894
 USER-SPECIFIED RUNOFF COEFFICIENT = .8618
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF (CFS) = 1.21

TOTAL AREA (ACRES) = 0.36 TOTAL RUNOFF (CFS) = 1.21
*************
 FLOW PROCESS FROM NODE 80.00 TO NODE 90.00 IS CODE = 21
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 87.00
 UPSTREAM ELEVATION(FEET) = 640.20
 ELEVATION (FEET) = 637.70

ELEVATION DIFFERENCE (FEET) = 2.50


TC = 0.323*[( 87 00**2)'
                          2.50)]**.2 =
 COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.297
 USER-SPECIFIED RUNOFF COEFFICIENT = .8647
 SOIL CLASSIFICATION IS "B"
                      0.37
 SUBAREA RUNOFF(CFS) =
                    0.10 TOTAL RUNOFF(CFS) =
 TOTAL AREA(ACRES) =
******************
 FLOW PROCESS FROM NODE 100.00 TO NODE 110.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
_____
       ASSUMED INITIAL SUBAREA UNIFORM
       DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 167.00
 UPSTREAM ELEVATION(FEET) = 638.50
 DOWNSTREAM ELEVATION(FEET) =
                         634.50
 ELEVATION DIFFERENCE (FEET) =
                           4.00
 TC = 0.323*[(167.00**3)/(4.00)]**.2 = 5.273
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.190
 USER-SPECIFIED RUNOFF COEFFICIENT = .8640
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) =
```

```
TOTAL AREA(ACRES) = 0.20 TOTAL RUNOFF(CFS) =
******************
 FLOW PROCESS FROM NODE 120.00 TO NODE 130.00 IS CODE = 21
______
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<
______
      ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 117.00
 UPSTREAM ELEVATION(FEET) = 639.50
 DOWNSTREAM ELEVATION (FEET) =
                      638.00
 ELEVATION DIFFERENCE (FEET) = 1.50
TC = 0.323*[( 117.00**3)/( 1.50)]**.2 =
                                  5.182
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.225
 USER-SPECIFIED RUNOFF COEFFICIENT = .8642
 SOIL CLASSIFICATION IS "B"
                   0.95
 SUBAREA RUNOFF (CFS) =
 TOTAL AREA(ACRES) =
                  0.26 TOTAL RUNOFF(CFS) =
*****
 FLOW PROCESS FROM NODE 140.00 TO NODE 150.00 IS CODE = 21
 _____
 >>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS
_____
      ASSUMED INITIAL SUBAREA UNIFORM
      DEVELOPMENT IS APARTMENT
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 154.00
 UPSTREAM ELEVATION (FEET) = 637.00
 DOWNSTREAM ELEVATION (FEET) = 635.50
 ELEVATION DIFFERENCE (FEET) = 1.50
TC = 0.323*[( 154.00**3)/( 1.50)]**.2 = 6.111
 100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 3.907
 USER-SPECIFIED RUNOFF COEFFICIENT = .8619
 SOIL CLASSIFICATION IS "B"
 SUBAREA RUNOFF(CFS) = 0.61
TOTAL AREA(ACRES) = 0.18 TOTAL RUNOFF(CFS) = 0.61
______
 END OF STUDY SUMMARY:
                       0.2 TC(MIN.) =
 TOTAL AREA (ACRES) =
                                      6.11
 PEAK FLOW RATE(CFS) =
                      0.61
______
```


END OF RATIONAL METHOD ANALYSIS

APPENDIX 5

PONDING EXHIBIT & STREET CAPACITY CROSS SECTIONS



LEGEND




PONDED AREA

PROPOSED STORM DRAIN EXISTING STORM DRAIN WATER SURFACE ELEVATION (100 YEAR STORM) SECONDARY OVERFLOW DIRECTION



PONDING EXHIBIT WEST 2ND APARTMENT CORONA, CALIFORNIA




54 inch - Pipe

Project Description		
Friction Method	Manning Formula	
Solve For	Discharge	
Input Data		
Roughness Coefficient	0.013	
Channel Slope	0.020 ft/ft	
Normal Depth	54.0 in	
Diameter	54.0 in	


Channel Slope (ft/ft)	Discharge (cfs)	Velocity (ft/s)	Flow Area (ft²)	Wetted Perimeter (ft)	Top Width (ft)
0.005	139.04	8.74	15.9	14.1	0.00
0.006	152.32	9.58	15.9	14.1	0.00
0.007	164.52	10.34	15.9	14.1	0.00
0.008	175.88	11.06	15.9	14.1	0.00
0.009	186.55	11.73	15.9	14.1	0.00
0.010	196.64	12.36	15.9	14.1	0.00
0.011	206.24	12.97	15.9	14.1	0.00
0.012	215.41	13.54	15.9	14.1	0.00
0.013	224.20	14.10	15.9	14.1	0.00
0.014	232.67	14.63	15.9	14.1	0.00
0.015	240.83	15.14	15.9	14.1	0.00
0.016	248.73	15.64	15.9	14.1	0.00
0.017	256.39	16.12	15.9	14.1	0.00
0.018	263.82	16.59	15.9	14.1	0.00
0.019	271.05	17.04	15.9	14.1	0.00
0.020	278.09	17.49	15.9	14.1	0.00

Cross Section for BV-1




Cross Section for BV-2

Project Description		_
Friction Method	Manning Formula	Q100 PER CITY OF CORONA SD HYDROLOGY CALCULATION
Solve For	Normal Depth	THEROLOGY GALCOLATION
Input Data		54151111510
Channel Slope	0.020 ft/ft	54" FULL FLOV PIPE@2%
Normal Depth	12.8 in	\bigvee
Discharge	325.00 cfs = 602.9	8 CFS - 278.09 CFS



Cross Section for BV-3

Project Description		_
Friction Method	Manning Formula	Q100 PER CITY OF CORONA SD HYDROLOGY CALCULATION
Solve For	Normal Depth	THE NOTE OF CALCOLLY HELD
Input Data		54" FULL FLOV
Channel Slope	0.020 ft/ft	PIPE@2%
Normal Depth	12.2 in	\forall
Discharge	325.00 cfs = 60	02.98 CFS - 278.09 CFS



Cross Section for 2nd-4

Project Description		
Friction Method	Manning Formula	
Solve For	Normal Depth	
Input Data		
Channel Slope	0.020 ft/ft	
Normal Depth	17.9 in	
Discharge	602.98 cfs	

