



NOTES:

1. GROUND SHALL BE PRE-WETTED PER SOILS ENGINEER'S DIRECTION PRIOR TO PLACEMENT OF CONCRETE.
2. MATERIAL FOR CONSTRUCTION OF DOWN DRAIN SHALL BE CONCRETE REINFORCED WITH 6"X 6" W1.4 X W1.4 WELDED WIRE FABRIC.
3. DOWN DRAIN TO PIPE TRANSITION SHALL BE SET 2' MIN. FROM ROAD RIGHT-OF-WAY.



APPROVED BY:
Kip D. Field
 CITY ENGINEER
 KIP D. FIELD

11/23/09
 DATE

CITY OF CORONA

**DOWN DRAIN TO
 CULVERT TRANSITION**

REVISION	DESCRIPTION	BY	DATE

STANDARD PLAN NUMBER: **223** SHT 1 OF 1