



FRONDS TO REMAIN TIED UP UNTIL DIRECTED BY CITY TO REMOVE TIES. TIES TO BE JUTE OR OTHER ORGANIC TWINE.

INSTALL 3"x 3' DIAMETER OF MULCH AROUND BASE OF PALM.

BACKFILL WITH WASHED PLASTER SAND.

THE PLANTING PIT IS TO BE 2X WIDTH AND 2X DEPTH OF THE ROOT BALL.

4" CAP SECURED TO PIPE WITH SCREWS.

4" HIGH WATER BASIN TEMPORARILY

4" PERFORATED PVC PIPE WRAPPED WITH FILTER FABRIC.

FILTER FABRIC

4" DIA. BY 24" LONG PERFORATED PIPE W/ 3/4" CRUSHED ROCK.

NOTE:

1. PLANT PALM WITH THE TRUNK PLUMB.
2. CONTACT PARK DIVISION AT (951) 817-5728 48 HOURS IN ADVANCE TO LOCATE THE STREET TREES.
3. ALL BACKFILL TO BE WATER JETTED DURING PLANTING FOR MAXIMUM STABILITY.
4. QUEEN PALMS NEED STAKING.
5. SPREAD 1/2 CUP OF 10-10-10 COMMERCIAL FERTILIZER AROUND ROOT BALL SURFACE.

6. STREET TREES ARE SPACED AT 35' O.C. EXCEPT WHERE FIELD CONDITIONS OBSTRUCT TREE PLANTING IN WHICH CASE TREE SPACING AND TOTAL TREES PLANTED MAY VARY FROM THE NUMBER APPROVED ON THE PLANS.
7. BROWN TRUNK SIZE SHALL BE FROM TOP OF ROOTBALL TO 1ST GREEN PETIOLE.



APPROVED BY: *KIP D. FIELD* 11/23/09
 CITY ENGINEER DATE
 KIP D. FIELD

CITY OF CORONA
 STREET TREE PLANTING
 (PALM TREE)

| REVISION | DESCRIPTION | BY | DATE |
|----------|-------------|----|------|
| | | | |

STANDARD PLAN NUMBER: **616** SHT 1 OF 1