



FIELD INSPECTION REQUIREMENTS

THE DEVELOPER/CONTRACTOR SHALL CONTACT THE CITY'S PARKS DEPARTMENT INSPECTOR AT (951) 817-5728 AT LEAST 48 HOURS IN ADVANCE TO INSPECT THE FOLLOWING:

1. PRE-JOB CONFERENCE WITH CITY APPROVED PLANS AT THE WORKSITE.
2. COMPLETION OF ROUGH GRADE, AND IDENTIFICATION OF ALL PROPERTY LINES.
3. LAYOUT OF HARDSCAPE FORMS PRIOR TO POUR.
4. IRRIGATION INSTALLATION AT THE FOLLOWING POINTS:
 - A. METER AND CONTROLLER PEDESTAL LOCATION
 - B. TRENCHING (TO CHECK MAINLINE AND LATERAL LINE DEPTH).
 - C. SLEEVE LOCATIONS.
 - D. MAINLINE INSTALLATION WITH PRESSURE TEST AT 150 PSI FOR 4 HOURS.
 - E. POINT OF CONNECTION TO MAIN.
 - F. BACKFLOW PREVENTION DEVICE INSTALLATION PRIOR TO BACKFILL.
 - G. CONTROL VALVE INSTALLATION.
 - H. HEAD AND SWING JOINT INSTALLATION.
 - I. HEAD COVERAGE.
5. ROCK REMOVAL AND FINISHED GRADE PREPARATION.
6. CALSENSE CERTIFICATION AND LOCAL RADIO TESTING.
7. FLOOD TEST OF FINISHED GRADE.
8. WEED ABATEMENT.
9. PLANT LAYOUT.
10. ACCEPTANCE OF PLANT QUALITY AND QUANTITY AT DELIVERY SITE.
11. PLANT INSTALLATION.
12. 30, 60, 90 DAY PLANT MAINTENANCE REVIEW.
13. FINAL INSPECTION.
14. ADDITIONAL INSPECTIONS WILL BE REQUIRED TO COMPLY WITH VARIOUS DEVELOPMENT PERMIT REQUIRED BY THE CITY OF CORONA. THE CONTRACTOR SHALL CONTACT THE APPROPRIATE CITY AGENCY.
 - SEWER, UTILITIES, WALLS, BUILDING, ELECTRICAL - BUILDING AND SAFETY
 - EROSION CONTROL, STREET IMPROVEMENTS, SITE DRAINAGE - PUBLIC WORKS
 - RECYCLED WATER INSPECTION - CORONA WATER & POWER DEPARTMENT

(TO BE PLACED ON)
(ALL PARK PLANS)



APPROVED BY:

 11/23/09
 CITY ENGINEER DATE
 KIP D. FIELD

CITY OF CORONA

FIELD INSPECTION REQUIREMENTS

REVISION	DESCRIPTION	BY	DATE

STANDARD PLAN NUMBER: **831** SHT 1 OF 1