



FIELD INSPECTION REQUIREMENTS

THE DEVELOPER/CONTRACTOR SHALL CONTACT THE CITY'S PUBLIC WORKS DEPARTMENT, INSPECTION SECTION (951) 736-2442 AND/OR PARKS DEPARTMENT INSPECTOR AT (951) 817-5728 AT LEAST 48 HOURS IN ADVANCE TO INSPECT THE FOLLOWING:

1. PRE-JOB CONFERENCE WITH CITY APPROVED PLANS AT THE WORKSITE.
2. COMPLETION OF FINISHED GRADE.
 - A. SURVEY AND IDENTIFY ALL PROPERTY LINES AND THEIR POINTS OF BEARING.
3. LAYOUT OF WOOD OR CONCRETE HEADERS BUT PRIOR TO INSTALLATION.
4. IRRIGATION INSTALLATION AT THE FOLLOWING POINTS:
 - A. METER AND CONTROLLER PEDESTAL LOCATION (TO BE APPROVED BY PUBLIC WORKS INSPECTOR.)
 - B. TRENCHING (TO CHECK DEPTH).
 - C. SLEEVING.
 - D. MAINLINE INSTALLATION WITH PRESSURE TEST AT 150 PSI FOR 4 HOURS.
 - E. POINT OF CONNECTION TO MAIN.
 - F. BACKFLOW PREVENTION DEVICE INSTALLATION PRIOR TO BACKFILL.
 - G. CONTROL VALVE INSTALLATION.
 - H. HEAD AND SWING JOINT INSTALLATION.
 - I. HEAD COVERAGE.
5. ROCK REMOVAL LARGER THAN 1/2" IN DIAMETER.
6. CALSENSE CERTIFICATION AND LOCAL RADIO TESTING.
7. FLOOD TEST.
8. WEED ABATEMENT.
9. PLANT LAYOUT.
10. ACCEPTANCE OF PLANT QUALITY AND QUANTITY AT DELIVERY SITE.
11. PLANT INSTALLATION.
12. FINAL INSPECTION.

(TO BE PLACED ON
ALL CFD/LMD PLANS)



APPROVED BY:

 11/23/09
 CITY ENGINEER DATE
 KIP D. FIELD

CITY OF CORONA

FIELD INSPECTION REQUIREMENTS

REVISION	DESCRIPTION	BY	DATE

STANDARD PLAN NUMBER: **630** SHT 1 OF 1